GENERAL INDEX


INCLUDED THIS PROJECT		BEGIN WITH SHEET
[X]	ROADWAY	1
[ ]	PERMANENT SIGNS	1001
[ ]	TRAFFIC SIGNALS	2001
[ ]	ITS COMPONENTS	3001
[ ]	LIGHTING	4001
[ ]	(RESERVED)	5001
[X]	ROADWAY STD. DWGS	6001
[ ]	BOX CULVERT STD. DWGS (LRFD)	7001
[ ]	BOX CULVERT STD. DWGS (STD. SPEC.)	7501
[X]	BRIDGE	8001
[X]	CROSS SECTIONS	9001

STATE OF MISSISSIPPI
CITY OF JACKSON

PLAN AND PROFILE OF PROPOSED CITY STREET
FEDERAL AID PROJECT NO. STP-7287-00(001)LPA

CITY OF JACKSON - RECONSTRUCTION OF THE MCCLUER ROAD BRIDGE AT CANY CREEK TRIBUTARY

HINDS COUNTY



STATE MAP

NOTE
★ INDICATES APPROXIMATE LOCATION OF PROJECT.


LAT. 32°14'25.62"N LONG. 90°14'10.04"W
(APPROX. MIDDLE OF PROJECT)

BRIDGE STRUCTURES REQ'D.

BRIDGE NO. SA25-157
MCCLUER RD ACROSS
CANY CREEK TRIBUTARY
STA. 10+01.02
SPANS = 2 @ 19'
SKEW = NONE
LENGTH = 37.96'

BOX BRIDGES REQ'D.

N/A



DESIGN CONTROL

35 MPH = V (SPEED DESIGN)

ADT (2025) = 3,100 : ADT (2045) = 3443
DHV = : D = % T = %

PERMITS ACQUIRED BY LPA

WETLANDS AND WATERS PERMITS

	WATERS	WETLANDS
NATIONWIDE #14	[Y]	[N]
NATIONWIDE (OTHER)*	[N]	[N]
GENERAL*	[N]	[N]
INDIVIDUAL (404)*	[N]	[N]

STORMWATER PERMIT [N]

Y REQUIRED, CNOI SUBMITTED BY MDOT (DISTURBED AREA=5 ACRES)

S REQUIRED, SCNOI TO BE SUBMITTED BY CONTRACTOR (1 TO 4.99 ACRES)

N NO STORMWATER PERMIT REQUIRED (<1 ACRE)

APPROVED BY: _____

CONVENTIONAL SYMBOLS

COUNTY LINE
TOWN CORP LINE
SECTION LINE
DEED LINE
EXISTING ROADWAY
PROPOSED ROADWAY
RAILROAD
BRIDGES

LENGTH DATA

LENGTH OF ROADWAY	162.04	FT. 0.031 MI.
LENGTH OF BRIDGES	37.96	FT. 0.007 MI.
LENGTH OF PROJECT (NET)		FT. 0.038 MI.
LENGTH OF EXCEPTIONS	0.00	FT. 0.000 MI.
LENGTH OF PROJECT (GROSS)		FT. 0.038 MI.

EQUATIONS

N/A

SCALES

PLAN 1 IN.= 100 FT.
PROFILE {HOR. 1 IN.= 100 FT. / VERT. 1 IN.= 10 FT.
LAYOUT 1 IN.= 600 FT.

EXCEPTIONS

N/A

DESIGNED BY: PICKERING

CONSTRUCTION PROJECT DATA

EXTERNAL PROJECT NUMBER	STP-7287-00(001)LPA
FMS & DETAIL	109860/701000

P S & E DATE: 06/26/2026

APPROVED:

JOHN HORHN, MAYOR

KOHL BOOZER, P.E.
LICENSE NO. 35697

KOHL BOOZER LICENSED PROFESSIONAL ENGINEER 35697 STATE OF MISSISSIPPI
06/26/2026

TITLE SHEET
9/14/2026 3:00:36 PM Title.dgn

DESCRIPTION OF SHEET	REV. DATE	WKG. NO.	SH. NO.
TITLE SHEET (1)			1
DETAILED INDEX & GENERAL NOTES (3)			
DETAILED INDEX		DI- 1	2
GENERAL NOTES		GN- 1	3
GENERAL NOTES		GN- 2	4
TYPICAL SECTION SHEETS (2)			
TYPICAL SECTION - MCCLUER RD		TS- 1	5
TYPICAL SECTION - MCCLUER RD		TS- 2	6
SUMMARY OF QUANTITIES (2)			
SUMMARY OF QUANTITIES		SQS- 1	7
SUMMARY OF QUANTITIES		SQS- 2	8
ESTIMATED QUANTITIES (4)			
ESTIMATED QUANTITIES		EQ- 1	9
ESTIMATED QUANTITIES		EQ- 2	10
ESTIMATED QUANTITIES		EQ- 3	11
STANDARD ROADSIDE SIGNS		SRS- 1	12
PLAN & PROFILE SHEETS (1)			
MCCLUER RD. - STA. 9+40 TO STA. 11+40		WK- 3	13
PAVEMENT MARKING DETAILS (1)			
PAVEMENT MARKING DETAILS: MCCLUER RD. - STA. 9+40 TO STA. 11+40		PMD- 1	14
TRAFFIC CONTROL PLAN (2)			
CONSTRUCTION SIGNING - MCCLUER RD.		CS- 1	15
TRAFFIC CONTROL PLAN - MCCLUER RD.		TC- 1	16
EROSION CONTROL SHEETS (1)			
EROSION CONTROL PLAN - MCCLUER RD.		ECP- 3	17
SPECIAL DESIGN SHEETS (2)			
VEGETATION SCHEDULE		VS- 1	18
SIGN SUPPORT HARDWARE 2.0" SQUARE POST		SDTSS- 1	19
STANDARD DRAWINGS - ROADWAY SHEETS (24)			
PAVEMENT MARKING DETAILS FOR 2- LANE & 4- LANE DIVIDED ROADWAYS	4/22/26	PM- 1	6051
TYPICAL TEMPORARY EROSION CONTROL/SEDIMENT CONTROL APPLICATIONS		ECD- 1	6101
DETAILS OF SEDIMENT BARRIER APPLICATIONS		ECD- 2	6102
DETAILS OF SILT FENCE INSTALLATION		ECD- 3	6103
DITCH CHECK STRUCTURES, TYPICAL APPLICATIONS AND DETAILS		ECD- 4	6104
TEMPORARY EROSION, SEDIMENT, & WATER POLLUTION CONTROL MEASURES (SILT FENCE & HAY BALE DITCH CHECKS)		ECD- 5	6105
DETAILS OF EROSION CONTROL WATTLE DITCH CHECK		ECD- 6	6106
DETAILS OF EROSION CONTROL SILT DIKE DITCH CHECK		ECD- 7	6107
ROCK DITCH CHECK		ECD- 8	6108
ROCK FILTER DAM		ECD- 9	6109
ROCK DITCH CHECK WITH SUMP EXCAVATION AND ROCK FILTER DAM		ECD- 10	6110
DETAILS OF EROSION CONTROL SANDBAG DITCH CHECK		ECD- 21	6121
SEDIMENT RETENTION BARRIER		ECD- 22	6122
DETAILS OF TYPICAL DITCH TREATMENTS		DT- 1	6123
GUARDRAIL: "W" BEAM (STEEL POSTS)		GR- 1B	6203
GUARDRAIL: BRIDGE END SECTION- TYPE A & C		GR- 2	6204
GUARDRAIL: TYPICAL INSTALLATION AT BRIDGE APPROACHES FOR 2- LANE, 2- WAY HIGHWAY		GR- 4A	6215
GUARDRAIL: MISCELLANEOUS HARDWARE		GR- HW	6221
STANDARD ROADSIDE SIGN ASSEMBLY AND INSTALLATION	12/11/25	SN- 4	6306
STANDARD ROADSIDE SIGN ASSEMBLY AND INSTALLATION		SN- 4A	6307
TYPICAL INSTALLATION AND DETAILS OF DELINEATORS AND DISTANCE REFERENCE SIGNS	12/11/27	SN- 8	6314
TYPICAL GUARDRAIL DELINEATION	12/11/28	SN- 8C	6317
SIGNING DETAILS FOR BRIDGE APPROACHES	12/11/29	SN- 9	6318
HIGHWAY SIGN AND BARRICADE DETAILS FOR CONSTRUCTION PROJECTS	12/11/30	TCP- 8	6358
CROSS SECTIONS (2)			
DIXON RD			9001- 9002
TOTAL EXCLUDING BRIDGE SHEETS =			45

BRIDGE SHEET
NOTE: SEE SHEET DI- BR FOR DETAILS

KOHL BOOZER LLP
LICENSED PROFESSIONAL ENGINEER
35697
STATE OF MISSISSIPPI
06/26/2026

CITY OF JACKSON

DESIGNED BY: RKB
DETAILED BY: RKB
CHECKED BY: FMT
DATE: 6/26/2026

FMS CON: 109860/701000
PROJECT NO.: STP-7287-00(001)LPA
COUNTY: HINDS

DETAILED INDEX

SHEET ID
DI-1

SHEET NO.
2

PLAN SHEET
6/26/2026 2:07:36 PM DI.dgn

GENERAL NOTES

BRIDGES AND WALLS

(1) THE BRIDGE DECKS SHALL BE GROOVED AND ALL BRIDGE JOINTS SHALL BE SEALED PRIOR TO OPENING THE BRIDGES TO TRAFFIC.

(2) STORAGE OF FLAMMABLE MATERIALS WILL NOT BE ALLOWED UNDER ANY BRIDGE STRUCTURES WITHOUT WRITTEN APPROVAL FROM THE PROJECT ENGINEER. SEE NOTICE TO BIDDERS ENTITLED "MATERIAL STORAGE UNDER BRIDGES" FOR MORE INFORMATION.

DRAINAGE STRUCTURES

(3) THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROTECTING EXISTING STRUCTURES SUCH AS, BUT NOT LIMITED TO, PIPES, INLETS, APRONS, AND BRIDGES FROM DAMAGE WHICH MIGHT OCCUR DURING CONSTRUCTION. THE CONTRACTOR SHALL REPLACE OR REPAIR, AS DIRECTED BY THE ENGINEER, ANY STRUCTURES DAMAGED DURING THE LIFE OF THE CONTRACT. NO PAYMENT WILL BE MADE FOR REPLACEMENT OR REPAIR OF DAMAGED ITEMS.

EARTHWORK

(4) 25% SHRINKAGE FACTOR USED IN THE EARTHWORK CALCULATIONS IS FOR DESIGN ESTIMATING PURPOSES ONLY.

(5) VOIDS CREATED BY THE REMOVAL OF, BUT NOT LIMITED TO, POSTS, CONCRETE ANCHORS, AND FOOTINGS SHALL BE BACKFILLED AND TAMPED IN ACCORDANCE WITH SECTION 203 OF ***THE MISSISSIPPI STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION***, THE COST OF WHICH WILL BE ABSORBED IN OTHER ITEMS BID.

(6) WORK ON STRUCTURES FOR THIS PROJECT REQUIRES EXCAVATION IN THE IMMEDIATE VICINITY OF TRAFFIC AND ADJACENT PROPERTIES. THEREFORE, THE RISK OF A FAILURE OCCURRING DURING EXCAVATION REQUIRES THAT EXTREME CAUTION BE EXERCISED. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PLACING WHAT BRACING, SHORING, OR GROUND SUPPORT SYSTEM THAT IS DEEMED NECESSARY TO PREVENT A FAILURE AND PROTECT THE PERSONS WORKING NEAR THE EXCAVATION, THE PUBLIC THAT MAY BE ABOVE THE EXCAVATION, OR ANY STRUCTURES ADJACENT TO THE EXCAVATION. ALL COSTS FOR DESIGNING, DRAWING, AND CONSTRUCTING THE FACILITY SHALL BE INCLUDED IN THE PRICE BID FOR CONTRACT ITEMS.

(7) SMALL AMOUNTS OF EXCAVATION MAY BE NECESSARY AT SOME OF THE SITES. THIS MATERIAL MAY BE USED AS E.S.F.E. MATERIAL AND WILL BE PAID FOR AS BORROW. NO E.S.F.E. MATERIAL SHALL BE REMOVED FROM THE PROJECT WITHOUT THE APPROVAL OF THE ENGINEER.

(8) VEGETATIVE MATERIAL WILL BE REMOVED PRIOR TO PLACEMENT OF GRANULAR MATERIAL. THE COST OF WHICH SHALL BE ABSORBED IN OTHER ITEMS BID.

(9) THIN LAYERS OF ROCK ENCOUNTERED DURING EXCAVATION WILL BE PAID FOR AS UNCLASSIFIED EXCAVATION. SOLID ROCK AS SHOWN ON PLANS AND CROSS SECTIONS WILL BE PAID FOR AS ROCK EXCAVATION.

ENVIRONMENTAL & CLEARING

(10) NO TEMPORARY CULVERT STREAM CROSSINGS WILL BE ALLOWED.

EROSION CONTROL - TEMPORARY

(11) WIRE FENCE BACKING WILL BE REQUIRED FOR ALL SILT FENCE. (SEE WK. NO. ECD-3)

(12) THE EROSION CONTROL DEVICES REFERENCED IN THESE PLANS ARE A MINIMUM REQUIREMENT. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO ENSURE THAT SILT DOES NOT LEAVE THE RIGHT OF WAY OR CONTAMINATE WATERS OF THE U. S. DURING CONSTRUCTION. THE CONTRACTOR SHALL SUBMIT AN EROSION CONTROL PLAN PRIOR TO COMMENCEMENT OF WORK AND MAINTAIN THE PLAN DURING CONSTRUCTION. ANY ADDITIONAL SILT BASINS NOT SHOWN IN THE PLANS SHALL BE INCLUDED IN THE CONTRACTOR'S EROSION CONTROL PLAN PRIOR TO SUBMITTING FOR APPROVAL.

(13) ALL ITEMS OF WORK ASSOCIATED WITH THE INSTALLATION OF A CONSTRUCTION ENTRANCE SHALL BE ABSORBED IN OTHER ITEMS OF WORK.

PAVEMENT, BASE, AND SHOULDERS

(14) THE CONTRACTOR SHALL REPAIR ANY DAMAGE TO THE PAVED OR UNPAVED SHOULDER THAT MIGHT OCCUR DURING CONSTRUCTION. ANY REPAIR TO SHOULDER WILL BE IN ACCORDANCE WITH THE APPLICABLE SECTIONS OF ***THE MISSISSIPPI STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION***. NO PAYMENT WILL BE MADE FOR REPAIR OF DAMAGED SHOULDER.

(15) WHERE MILLING IS REQUIRED, THE CONTRACTOR SHALL PROVIDE OUTLETS IN THE EXISTING SHOULDERS AT SUFFICIENT INTERVALS TO PREVENT POOLING OR STANDING WATER ON THE MILLED SURFACE, THE COST OF WHICH SHALL BE ABSORBED IN OTHER ITEMS BID.

GENERAL NOTES (CONT.)

PLANS

(16) IF COLORS ARE USED ON PLAN/PROFILE SHEETS, THEY ARE INTENDED TO VISUALLY EASE THE LOCATION OF ELEMENTS FOR USERS OF THESE DRAWINGS. ALTHOUGH THE INTENT IS TO CATEGORIZE EVERYTHING AS EITHER EXISTING OR PROPOSED, IT IS THE END USER'S RESPONSIBILITY TO ENSURE ALL ELEMENTS ARE INTERPRETED CORRECTLY, REGARDLESS OF COLOR.

ROADSIDE BARRIERS

(17) ALL DIMENSIONS AND SPACINGS FOR BRIDGE RAIL CONNECTORS SHALL BE VERIFIED IN THE FIELD BY THE CONTRACTOR PRIOR TO FABRICATION.

TRAFFIC CONTROL - PERMANENT

(18) ALL POST, PIPE, AND I-BEAM LENGTHS IN THESE PLANS ARE ESTIMATES. POST LENGTHS FOR ALL SIGNS SHALL BE VERIFIED IN THE FIELD BY THE CONTRACTOR PRIOR TO FABRICATION.

(19) ALL EXISTING SIGNS WHICH ARE TO BE REMOVED AS A PART OF THIS PROJECT THAT ARE NOT IN CONFLICT WITH CONSTRUCTION SHALL REMAIN IN PLACE UNTIL NEW SIGNS ARE INSTALLED UNLESS NOTED OR DIRECTED OTHERWISE BY THE PROJECT ENGINEER. ROADWAY SIGNS THAT ARE IN CONFLICT WITH CONSTRUCTION SHALL BE REMOVED AND RELOCATED BY THE CONTRACTOR AS DIRECTED BY THE ENGINEER, THE COST OF WHICH SHALL BE ABSORBED IN OTHER ITEMS BID.

(20) DIRECT-APPLIED LEGEND, BORDER, AND/OR SHIELDS ARE TO BE USED ON ALL SIGNS. DIGITALLY PRODUCED SIGN COPY, SHIELDS, LEGEND, SYMBOLS, OR IMAGES WILL NOT BE ALLOWED WITHOUT WRITTEN APPROVAL FROM THE PROJECT ENGINEER.

(21) ALL PERMANENT SIGNS SHALL CONFORM TO THE LATEST EDITION OF THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES.

(22) ALL SIGN LOCATIONS SHALL BE APPROVED BY THE PROJECT ENGINEER PRIOR TO INSTALLATION.

(23) THE RETROREFLECTIVE SIGN SHEETING ON PERMANENT GROUND-MOUNTED SIGNS SHALL BE AS FOLLOWS: BROWN BACKGROUND SHEETING ON GUIDE SIGNS SHALL BE MINIMUM TYPE VIII; GREEN AND BLUE BACKGROUND SHEETING ON GUIDE SIGNS SHALL BE MINIMUM TYPE IX; ALL WHITE, YELLOW, FLUORESCENT YELLOW AND FLUORESCENT YELLOW/GREEN SHEETING SHALL BE TYPE XI. ALL SIGN SHEETING ON OVERHEAD SIGNS SHALL BE TYPE XI.

(24) ALL EXISTING SIGNS AND SUPPORTS REMOVED UNDER THIS PROJECT SHALL BECOME THE PROPERTY OF THE CONTRACTOR AND ARE NOT A SEPARATE PAY ITEM.

(25) REMOVAL OF RAISED PAVEMENT MARKERS THAT ARE IN CONFLICT WITH REQUIRED CONSTRUCTION IS NOT CONSIDERED A SEPARATE PAY ITEM. COST TO BE ABSORBED IN OTHER ITEMS BID.

(26) REMOVAL OF OBJECT MARKERS IS NOT CONSIDERED A SEPARATE PAY ITEM, AND SHALL BE ABSORBED IN OTHER ITEMS BID.

TRAFFIC CONTROL - TEMPORARY

(27) THE LOCATION AND SPACING OF SIGNS, SHOWN ON THE TRAFFIC CONTROL PLANS, ARE APPROXIMATE AND MAY BE ADJUSTED AS NECESSARY TO FIT FIELD CONDITIONS.

(28) ALL TRAFFIC CONTROL DEVICES ON THIS PROJECT SHALL COMPLY WITH PART VI OF THE ***MUTCD*** (LATEST EDITION).

(29) ALL PLASTIC DRUMS SHALL HAVE A BALLASTING COLLAR MADE FROM RECYCLED TRUCK TIRES OR OTHER SUITABLE MATERIAL.

(30) FLUORESCENT ORANGE SHEETING SHALL BE USED ON ALL CONSTRUCTION AND TRAFFIC CONTROL SIGNS EXCEPT FOR THOSE DESIGNATED ON THE PLANS TO BE BLACK LEGEND AND BORDER ON WHITE BACKGROUND.

(31) THE CONTRACTOR SHALL COVER OR REMOVE ANY TEMPORARY TRAFFIC CONTROL SIGNS SHOWN IN THE TRAFFIC CONTROL PLAN THAT DO NOT APPLY TO THE CURRENT PHASE.

(32) THE RETROREFLECTIVE SIGN SHEETING ON RIGID, TEMPORARY TRAFFIC CONTROL (ORANGE) SIGNS SHALL BE MINIMUM TYPE IX.

UTILITIES

(33) UTILITIES ON THE DRAWINGS ARE SHOWN IN THEIR ORIGINAL LOCATION BASED UPON THE BEST INFORMATION AVAILABLE TO THE ENGINEER. UTILITIES THAT WERE FOUND TO BE IN CONFLICT WITH CONSTRUCTION HAVE BEEN RELOCATED. PERMITS ARE ON FILE WITH THE DEPARTMENT SHOWING THE APPROXIMATE LOCATION OF UTILITIES RELOCATED WITHIN THE RIGHT-OF-WAY. THE ENGINEER CAN NOT AND DOES NOT WARRANT THAT THIS INFORMATION IS COMPLETE OR ACCURATE. THE CONTRACTOR MUST COORDINATE DIRECTLY WITH THE INVOLVED UTILITY OWNERS TO HAVE UNDERGROUND UTILITY LINES FIELD LOCATED IN ADVANCE OF CONSTRUCTION.

(34) FOR LIST OF PUBLIC UTILITIES, SEE WORKING NO. 3.

KOHL BOOZER
LICENSED PROFESSIONAL ENGINEER
35697
STATE OF MISSISSIPPI
06/26/2026

CITY OF JACKSON

DESIGNED BY: RKB
DETAILED BY: RKB
CHECKED BY: FMT
DATE: 6/26/2026

FMS CON: 109860/701000
PROJECT NO.: STP-7287-00(001)LPA
COUNTY: HINDS

GENERAL NOTES

SHEET ID
GN-1

SHEET NO.
3

PLAN SHEET

6/26/2026 2:07:39 PM GN.dgn

GENERAL NOTES (CONT.)

MISCELLANEOUS

(35) SOME WORK IS REQUIRED OUTSIDE THE PROJECT LIMITS. NO ADDITIONAL COMPENSATION WILL BE MADE FOR SUCH WORK EXCEPT AS PROVIDED BY SPECIFIC PAY ITEMS INCLUDED IN THE PLANS.

(36) THE CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING AND RELOCATING MAIL BOXES AS NECESSARY TO MAINTAIN CONTINUOUS MAIL SERVICE THROUGHOUT THE LIFE OF THE PROJECT, THE COST OF WHICH SHALL BE ABSORBED IN OTHER ITEMS BID.

(37) THE CONTRACTOR IS RESPONSIBLE FOR FIELD-VERIFICATION OF EXISTING GRADES AND MAKING ADJUSTMENTS AS NECESSARY WITH THE APPROVAL OF THE PROJECT ENGINEER.

(38) THE CONTRACTOR SHALL COORDINATE AND CONDUCT WORK AT LOCAL ROADS AND DRIVEWAYS IN A MANNER SUCH THAT ACCESS IS NOT INTERRUPTED UNNECESSARILY. ACCESS SHALL BE PRESERVED IN THE BEST MANNER POSSIBLE. COORDINATION AND COMMUNICATION WITH LANDOWNERS MAY BE NECESSARY TO PREVENT INTERRUPTION OF DRIVEWAY ACCESS.

NOTICE:
THE NOTES CONTAINED HEREON ARE SPECIFIC TO THE SUBJECT PROJECT AND SHOULD BE REVIEWED IN DETAIL BY THE CONTRACTOR. PER SECTION 102.05 OF THE STANDARD SPECIFICATIONS, "THE BIDDER IS REQUIREDTO EXAMINE CAREFULLY THE SITE OF THE PROPOSED WORK, THE PROPOSAL, PLAN, STANDARD SPECIFICATIONS, SPECIAL PROVISION, NOTICES TO BIDDERS, AND CONTRACT FORMS BEFORE SUBMITTING A PROPOSAL."

KOHL BOOZER LEGEND PROFESSIONAL ENGINEER 35697 STATE OF MISSISSIPPI
06/26/2026

CITY OF JACKSON


DESIGNED BY: RKB
DETAILED BY: RKB
CHECKED BY: FMT
DATE: 6/26/2026

FMS CON: 109860/701000
PROJECT NO.: STP-7287-00(001)LPA
COUNTY: HINDS

GENERAL NOTES


SHEET ID **GN-2**
SHEET NO. **4**

6/26/2026 2:07:42 PM GN.dgn PLAN SHEET



TYPICAL SECTION

MCCLUER RD
STA. 9+40.00 TO STA. 9+81.02



SAFETY EDGE REQ'D
TOP 2 LIFTS ONLY
(NOT A PAY ITEM)
NEW CONSTRUCTION

1. 1.5" FINE MILLING REQ'D.
2. 1.5" 9.5–MM ST. ASPHALT PAVEMENT (1 @ 1.5") REQ'D.
3. 2" 12.5–MM ST. ASPHALT PAVEMENT (1 @ 2") REQ'D.
4. 3" 19–MM ST. ASPHALT PAVEMENT (1 @ 3") REQ'D.
5. 8" GRANULAR MATERIAL, CRUSHED STONE REQ'D.
6. GEOTEXTILE STABILIZATION, TYPE V, NON–WOVEN REQ'D.
7. 14.5" & VAR. CRUSHED STONE SHOULDER MATERIAL REQ'D.

TYPICAL SECTION

MCCLUER RD
STA. 9+81.02 TO STA. 10+01.02
STA. 10+38.98 TO STA. 10+58.98

KOHL BOOZER
LICENSED PROFESSIONAL ENGINEER
35697
STATE OF MISSISSIPPI
06/26/2026

CITY OF JACKSON

DESIGNED BY: RKB
DETAILED BY: RKB
CHECKED BY: FMT
DATE: 6/26/2026


FMS CON: 109860/701000
PROJECT NO.: STP-7287-00(001)LPA
COUNTY: HINDS

TYPICAL SECTIONS: MCCLUER RD

SHEET ID
TS-1

SHEET NO.
5

PLAN SHEET
6/26/2026 2:07:44 PM ts.dgn



TYPICAL SECTION

MCCLUER RD
STA. 10+58.98 TO STA. 11+40.00

(1) 1.5" FINE MILLING REQ'D.
(2) 1.5" 9.5–MM ST. ASPHALT PAVEMENT (1 @ 1.5") REQ'D.
(3) VAR. CRUSHED STONE SHOULDER MATERIAL REQ'D.

KOHL BOOZER
LICENSED PROFESSIONAL ENGINEER
35697
STATE OF MISSISSIPPI
06/26/2026

CITY OF JACKSON

DESIGNED BY: RKB
DETAILED BY: RKB
CHECKED BY: FMT
DATE: 6/26/2026

FMS CON: 109860/701000
PROJECT NO.: STP-7287-00(001)LPA
COUNTY: HINDS

TYPICAL SECTIONS: MCCLUER RD

SHEET ID
TS-2

SHEET NO.
6

PLAN SHEET
6/26/2026 2:07:44 PM ts.dgn

SUMMARY OF QUANTITIES (SHEET 1)

PAY ITEM NO.	PAY ITEM	UNIT	HINDS : 109860-701000		
			Prelim	Final	
201-A001	Clearing and Grubbing	LS	1		
202-B007	Removal of Asphalt Pavement, All Depths	SY	85		
202-B023	Removal of Bridge	EA	1		(1)
202-B136	Removal of Guard Rail	LF	52		
202-B215	Removal of Sign Including Post & Footing	EA	3		
203-A001	Unclassified Excavation, FM, AH	CY	15		(2)
203-G001	Excess Excavation, FM, AH	CY	350		(2)
209-A005	Geotextile Stabilization, Type V, Non-Woven	SY	127		
220-A001	Insect Pest Control	ACRE	1		
223-A001	Mowing	ACRE	1		
225-A001	Grassing	ACRE	1		
225-B001	Agricultural Limestone	TON	1		
225-C001	Mulch, Vegetative Mulch	TON	1		
907-234-A001	Temporary Silt Fence	LF	286		
237-A002	Wattles, 20"	LF	286		
304-D002	Granular Material, Crushed Stone	TON	175		(3)
	ALTERNATIVE ITEMS-CRUSHED STONE				
304-F001	3/4" and Down Crushed Stone Base	TON	50		(3)
	OR				
304-F002	Size 610 Crushed Stone Base	TON	50		(3)
	OR				
304-F003	Size 825B Crushed Stone Base	TON	50		(3)
907-403-A003	12.5-mm, ST, Asphalt Pavement	TON	10		
907-403-A006	19-mm, ST, Asphalt Pavement	TON	14		
907-403-A015	9.5-mm, ST, Asphalt Pavement	TON	29		
406-A002	Cold Milling of Bituminous Pavement, All Depths	SY	258		
407-A001	Asphalt for Tack Coat	GAL	33		
605-X003	Filter Material for Filter Beds, Type B	CY	263		
606-B002	Guard Rail, Class A, Type 1, 'W' Beam	LF	51		
606-D001	Guard Rail, Bridge End Section	EA	3		
606-E001	Guard Rail, Terminal End Section	EA	3		
907-618-A001	Maintenance of Traffic	LS	1		
619-D1001	Standard Roadside Construction Signs, Less than 10 Square Feet	SF	105		
619-D2001	Standard Roadside Construction Signs, 10 Square Feet or More	SF	117		
619-G4005	Barricades, Type III, Single Faced	LF	84		
620-A001	Mobilization	LS	1		
907-626-C013	6" Thermoplastic Edge Stripe, Continuous White	LF	400		
907-626-D006	6" Thermoplastic Traffic Stripe, Skip Yellow	LF	200		
907-627-L001	Two-Way Yellow Reflective High Performance Raised Markers	EA	6		
629-A001	Vehicular Impact Attenuator, 40 MPH	EA	1		
630-A003	Standard Roadside Signs, Sheet Aluminum, 0.125" Thickness	SF	18		
630-C005	Square Tube Posts, 2.0 lb/ft	LF	30		
630-F006	Delineators, Guard Rail, White	EA	10		
630-G003	Type 3 Object Markers, OM-3L, Post Mounted	EA	2		

(1) EXISTING BRIDGE 2 @ 19, TIMBER

(2) 25% SHRINKAGE FACTOR APPLIED AND ROUNDED TO THE NEAREST 5.

(3) 20% SHRINKAGE FACTOR APPLIED AND ROUNDED TO THE NEAREST 5.

KOHL BOOZER LICENSED PROFESSIONAL ENGINEER 35697 STATE OF MISSISSIPPI

06/26/2026

CITY OF JACKSON

DESIGNED BY: RKB

DETAILED BY: RKB

CHECKED BY: FMT

DATE: 6/26/2026

FMS CON: 109860/701000

PROJECT NO.: STP-7287-00(001)LPA

COUNTY: HINDS

SUMMARY OF QUANTITIES

SHEET ID SQS-1

SHEET NO. 7

PLAN SHEET

6/26/2026 2:07:45 PM sqs.dgn

SUMMARY OF QUANTITIES (SHEET 2)

PAY ITEM NO.	PAY ITEM	UNIT	HINDS : 109860-701000	
			Prelim	Final
630-G007	Type 3 Object Markers, OM-3R, Post Mounted	EA	2	
699-A001	Roadway Construction Stakes	LS	1	
907-803-B001	Conventional Static Pile Load Test	EA	1	
803-D007	HP 14 x 89 Steel Piling	LF	770	
907-803-I003	PDA Test Pile, HP Steel Pile	EA	1	
907-803-J001	Pile Restrike	EA	1	
907-804-A002	Bridge Concrete, Class AA	CY	3	
806-A001	19' Precast Concrete Slab Units, 3'-6" Interior	EA	12	
806-A009	19' Precast Concrete Slab Units, 3'-6" Exterior	EA	4	
806-C001	19' Precast Barrier Rail Units	EA	4	
815-A007	Loose Riprap, Size 300	TON	81	
815-E001	Geotextile under Riprap	SY	48	
907-831-PP001	Precast Panels	SY	72	
L00140: 806-D501	31' Precast Concrete Caps, Intermediate Unit	EA	1	
L00141: 806-E501	31' Precast Concrete Caps, End Unit with Wall	EA	2	

KOHL BOOZER
LICENSED PROFESSIONAL ENGINEER
35697
STATE OF MISSISSIPPI
06/26/2026

CITY OF JACKSON

DESIGNED BY: RKB
DETAILED BY: RKB
CHECKED BY: FMT
DATE: 6/26/2026

FMS CON: 109860/701000
PROJECT NO.: STP-7287-00(001)LPA
COUNTY: HINDS

SUMMARY OF QUANTITIES

SHEET ID
SQS-2

SHEET NO.
8

6/26/2026 2:07:48 PM sqs.dgn PLAN SHEET

REMOVAL ITEMS

WK. SH. NO.	STATION TO STATION		ASPHALT PAVEMENT	ASPHALT DRIVEWAYS	BRIDGE	GUARD RAIL	SIGNS	PIPES (ALL TYPES)	REMARKS
3	8+79.88	11+61.39	84.7		1.0	52.0	3.0		
UNITS			SQ. YDS.	SQ. YDS.	LIN. FT.	LIN. FT.	EA.	LIN. FT.	
TOTALS			85	0	1	52	3	0	

ESTIMATED EARTHWORK QUANTITIES

WORK SHEET NUMBER	CUT (C.Y.)	FILL (C.Y.)	BORROW (B9-6)	UNCLASSIFIED EXCAVATION	EXCAVATION		REMARKS
					EXCESS	SURPLUS	
WK-3	360	10					INCLUDES EMBANKMENT REMOVAL
UNIT	CU. YDS.	CU. YDS.					
SUBTOTAL	360	10					
EXCESS = (CUT) - (FILL)(1+SF)							
= 97 - (10*1.25)					348		
UNCLASSIFIED = (FILL)(1+SF)				13			
UNIT			CU. YDS.	CU. YDS.	CU. YDS.	CU. YDS.	
PROJECT TOTAL			0	13	348	0	

ESTIMATED TEMPORARY EROSION CONTROL ITEMS

WK. SH. NO.	TOTAL DITCH CHECKS	TEMPORARY SILT FENCE	WATTLES 20"	SILT DIKE	SANDBAGS
3		286	286		
TOTAL		LIN. FT.	LIN. FT.	LIN. FT.	EA
		286	286	0	0

GUARD RAIL REQUIRED

WK. NO.	STATION	STATE STD. (INSTALL)	GUARD RAIL LENGTHS				CABLE ANCHOR	TERMINAL SECTION	BRIDGE END SECTION	SINGLE DELINEATORS		REMARKS
			DIST. A	DIST. B	DIST. C	DIST. D	TYPE "1"		TYPE I	WHITE	YELLOW	
3	10+01.02	GR-4A	0.0	0	49.4	6.3		1	1	3		IA TAKING PLACE OF RT GUARDRAIL
3	10+39.98	GR-4A	80.6	38	49.4	6.3		2	2	7		
UNITS				L. F.		L. F.	EACH	EACH	EACH	EACH	EACH	
TOTALS				38		13	0	3	3	10	0	

SUMMARY OF PAVEMENT MARKINGS

WK SH NO.	STATION TO STATION		THERMOPLASTIC										CLEAR	MARKERS		
			CONTINUOUS		LEGEND		EDGE		DETAIL		SKIP			RED	YELLOW	
			WHITE	YELLOW	WHITE (LF)	WHITE (SF)	WHITE	YELLOW	WHITE	YELLOW	WHITE	YELLOW	CLEAR	CLEAR	1 WAY	2 WAY
3	9+40	11+40					400					200				6
UNITS			LIN. FT.	LIN. FT.	LIN. FT.	SQ. FT.	LIN. FT.	LIN. FT.	LIN. FT.	LIN. FT.	LIN. FT.	LIN. FT.	EA.	EA.	EA.	EA.
TOTAL			0	0	0	0	400	0	0	0	0	200	0	0	0	6

KOHL BOOLER
LICENSED PROFESSIONAL ENGINEER
35697
STATE OF MISSISSIPPI
06/26/2026

CITY OF JACKSON

DESIGNED BY: RKB
DETAILED BY: RKB
CHECKED BY: FMT
DATE: 6/26/2026

FMS CON: 109860/701000
PROJECT NO.: STP-7287-00(001)LPA
COUNTY: HINDS

ESTIMATED QUANTITIES

SHEET ID
EQ-1

SHEET NO.
9

PLAN SHEET

6/26/2026 2:07:52 PM EQ.dgn

SUMMARY OF TRAFFIC CONTROL ITEMS REQUIRED

WORKING NUMBER	PHASE OF CONST.	TEMPORARY PAINT OR TAPE								TRAFFIC STRIPE TAPE (TYPE 1)							BARRICADES						WARNING LIGHTS			FREE STANDING PLASTIC DRUMS	TRAFFIC CONTROL SIGNS																	REMARKS
		CONTINUOUS		SKIP		DETAIL		LEGEND		CONT. YELLOW	CONTINUOUS		SKIP		DETAIL	LEGEND	TYPE I		TYPE II		TYPE III		TYPE A	TYPE B	TYPE C		G20–1	G20–2	G20–4	R1–1	R11–2	R11–3A	R11–4	D3–1	M4–8A	M4–9L	M4–9R	M4–10L	M4–10R	W20–2	W13–1	W20–1		W16–8P	W20–3	
		WHITE	YELLOW	WHITE	YELLOW	WHITE	YELLOW	LIN. FT.	SQ. FT.	(TYPE I OR II)	WHITE	YELLOW	WHITE	YELLOW			SINGLE FACE	DOUBLE FACE	SINGLE FACE	DOUBLE FACE	SINGLE FACE	DOUBLE FACE																			36x36	48x48			
CS–1																					48										1	1	6	2	3	3	1	1	2		4				
UNITS		LIN. FT.	LIN. FT.	LIN. FT.	LIN. FT.	LIN. FT.	LIN. FT.	LIN. FT.	SQ. FT.	LIN. FT.	LIN. FT.	LIN. FT.	LIN. FT.	LIN. FT.	LIN. FT.	LIN. FT.	EACH	EACH	EACH	EACH	LIN. FT.	LIN. FT.	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH
TOTAL																					48										1	1	6	2	3	3	1	1	2		4				
TC–1	I																				36								2	2														
UNITS		LIN. FT.	LIN. FT.	LIN. FT.	LIN. FT.	LIN. FT.	LIN. FT.	LIN. FT.	SQ. FT.	LIN. FT.	LIN. FT.	LIN. FT.	LIN. FT.	LIN. FT.	LIN. FT.	LIN. FT.	EACH	EACH	EACH	EACH	LIN. FT.	LIN. FT.	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH
TOTAL																					36								2	2														
UNITS		LIN. FT.	LIN. FT.	LIN. FT.	LIN. FT.	LIN. FT.	LIN. FT.	LIN. FT.	SQ. FT.	LIN. FT.	LIN. FT.	LIN. FT.	LIN. FT.	LIN. FT.	LIN. FT.	LIN. FT.	EACH	EACH	EACH	EACH	LIN. FT.	LIN. FT.	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH
TOTAL																					84								2	2	1	1	6	2	3	3	1	1	2		4				

KOHL BOOZER LLP
LICENSED PROFESSIONAL ENGINEER
35697
STATE OF MISSISSIPPI
06/26/2026

CITY OF JACKSON

DESIGNED BY: RKB
DETAILED BY: RKB
CHECKED BY: FMT
DATE: 6/26/2026

FMS CON: 109860/701000
PROJECT NO.: STP-7287-00(001)LPA
COUNTY: HINDS

ESTIMATED QUANTITIES

SHEET ID **EQ-2**
SHEET NO. **10**

6/26/2026 2:07:54 PM EQ.dgn PLAN SHEET

SIGNS REQUIRED

SIGN NO.	SIZE	UNIT AREA FT²	QUAN. REQ'D.	TOTAL SIGN AREA FT²	REMARKS
G20 - 1	60" X 24"	10.00 ♦			ROAD WORK NEXT XX MILES
G20 - 2	36" X 18"	4.50			END ROAD WORK
G20 - 4	36" X 18"	4.50			PILOT CAR FOLLOW ME
[1] M1 - 1	24" X 24"	4.00			1 OR 2 DIGIT
[1] M1 - 1	30" X 24"	5.00			3 DIGIT
[2] M1 - 4	24" X 24"	4.00			1 OR 2 DIGIT
[2] M1 - 4	30" X 24"	5.00			3 DIGIT
[3] M1 - 5	24" X 24"	4.00			1 OR 2 DIGIT
[3] M1 - 5	30" X 24"	5.00			3 DIGIT
[4] M3 - 1	24" X 12"	2.00			NORTH- 1 OR 2 DIGIT RTE. MARKER
[4] M3 - 1	30" X 15"	3.13			NORTH- 3 DIGIT RTE. MARKER
[4] M3 - 2	24" X 12"	2.00			EAST- 1 OR 2 DIGIT RTE. MARKER
[4] M3 - 2	30" X 15"	3.13			EAST- 3 DIGIT RTE. MARKER
[4] M3 - 3	24" X 12"	2.00			SOUTH- 1 OR 2 DIGIT RTE. MARKER
[4] M3 - 3	30" X 15"	3.13			SOUTH- 3 DIGIT RTE. MARKER
[4] M3 - 4	24" X 12"	2.00			WEST- 1 OR 2 DIGIT RTE. MARKER
[4] M3 - 4	30" X 15"	3.13			WEST- 3 DIGIT RTE. MARKER
M4 - 8	24" X 12"	2.00			DETOUR- 1 OR 2 DIGIT RTE. MARKER
M4 - 8A	24" X 18"	3.00	2	6.00	END DETOUR
M4 - 9	48" X 36"	12.00 ♦			DETOUR ↑
M4 - 9L	48" X 36"	12.00 ♦	3	36.00	DETOUR ←
M4 - 9BL	48" X 36"	12.00 ♦			DETOUR ↰
M4 - 9SL	48" X 36"	12.00 ♦			DETOUR ↖
M4 - 9BSL	48" X 36"	12.00 ♦			DETOUR ↰
M4 - 9R	48" X 36"	12.00 ♦	3	36.00	DETOUR →
M4 - 9BR	48" X 36"	12.00 ♦			DETOUR ↱
M4 - 9SR	48" X 36"	12.00 ♦			DETOUR ↗
M4 - 9BSR	48" X 36"	12.00 ♦			DETOUR ↱
M4 - 10L	48" X 18"	6.00	1	6.00	DETOUR
M4 - 10R	48" X 18"	6.00	1	6.00	DETOUR
[4] M4 - 5	24" X 12"	2.00			TO
[4] M5 - 1L	21" X 15"	2.19			↰
[4] M5 - 1R	21" X 15"	2.19			↱
[4] M5 - 2L	21" X 15"	2.19			↰
[4] M5 - 2R	21" X 15"	2.19			↱
[4] M6 - 1L	21" X 15"	2.19			←
[4] M6 - 1R	21" X 15"	2.19			→
[4] M6 - 2L	21" X 15"	2.19			↖
[4] M6 - 2R	21" X 15"	2.19			↗
[4] M6 - 3	21" X 15"	2.19			↑

SIGNS REQUIRED (CONT'D)

SIGN NO.	SIZE	UNIT AREA FT²	QUAN. REQ'D.	TOTAL SIGN AREA FT²	REMARKS
(1) R1 - 1	36" OCTAGON	7.46	2	14.92	STOP
(2) R1 - 1	48" OCTAGON	13.25 ♦			
(2) R1 - 2	36" X 36" X 36"	3.90			YIELD
(1) R1 - 2	48" X 48" X 48"	6.93			
(2) R1 - 2	60" X 60" X 60"	10.83 ♦			
(1) R1 - 3	18" X 9"	1.13			3-WAY, 4-WAY, ETC.
(2) R1 - 3	24" X 12"	2.00			
(1) R2-1	24" X 30"	5.00			SPEED LIMIT
(2) R2-1	36" X 48"	12.00 ♦			
[6] R2-1	48" X 60"	20.00 ♦			
(1) R3-1	36" X 36"	9.00			
(2) R3-1	48" X 48"	16.00 ♦			
(1) R3-2	36" X 36"	9.00			
(2) R3-2	48" X 48"	16.00 ♦			
(1) R3-4	36" X 36"	9.00			
(2) R3-4	48" X 48"	16.00 ♦			
R3-5L	30" X 36"	7.50			ONLY
R3-5R	30" X 36"	7.50			ONLY
R3-6L	30" X 36"	7.50			↰
R3-6R	30" X 36"	7.50			↱
R3-7L	30" X 30"	6.25			LEFT LANE MUST TURN LEFT
R3-7R	30" X 30"	6.25			RIGHT LANE MUST TURN RIGHT
(1) R4-1	24" X 30"	5.00			DO NOT PASS
(2) R4-1	48" X 60"	20.00 ♦			
(1) R4-2	24" X 30"	5.00			PASS WITH CARE
(2) R4-2	48" X 60"	20.00 ♦			
R4-7	48" X 60"	20.00 ♦			↱
R4-8	48" X 60"	20.00 ♦			↰
R5-1	48" X 48"	16.00 ♦			DO NOT ENTER
R5-1a	42" X 30"	8.75			WRONG WAY
R6-1L	36" X 12"	3.00			ONE WAY
R6-1R	36" X 12"	3.00			ONE WAY
R6-2L	24" X 30"	5.00			ONE WAY ←
R6-2R	24" X 30"	5.00			ONE WAY →
R11-2	48" X 30"	10.00 ♦	2	20.00	ROAD CLOSED
R11-3a	60" X 30"	12.50 ♦	1	12.50	ROAD CLOSED XX MILES AHEAD
R11-3b	60" X 30"	12.50 ♦			BRIDGE OUT XX MILES AHEAD
R11-4	60" X 30"	12.50 ♦	1	12.50	ROAD CLOSED TO THRU TRAFFIC
R12-1	36" X 48"	12.00 ♦			WEIGHT LIMIT XX TONS
[7] R16-3	36" X 48"	12.00 ♦			WHEN WORKERS ARE PRESENT SPEEDING FINES DOUBLED
[6] [7] R16-3	48" X 60"	20.00 ♦			

SIGNS REQUIRED (CONT'D)

SIGN NO.	SIZE	UNIT AREA FT²	QUAN. REQ'D.	TOTAL SIGN AREA FT²	REMARKS
W1 - 1L	48" X 48"	16.00 ♦			↰
W1 - 1R	48" X 48"	16.00 ♦			↱
W1 - 2L	48" X 48"	16.00 ♦			↰
W1 - 2R	48" X 48"	16.00 ♦			↱
W1 - 3L	48" X 48"	16.00 ♦			↰
W1 - 3R	48" X 48"	16.00 ♦			↱
W1 - 4aL	48" X 48"	16.00 ♦			↰
W1 - 4aR	48" X 48"	16.00 ♦			↱
W1 - 5L	48" X 48"	16.00 ♦			↰
W1 - 5R	48" X 48"	16.00 ♦			↱
(1) W1 - 6L	48" X 24"	8.00			←
(2) W1 - 6L	60" X 30"	12.50 ♦			
(1) W1 - 6R	48" X 24"	8.00			→
(2) W1 - 6R	60" X 30"	12.50 ♦			
(1) W1 - 7	48" X 24"	8.00			↔
(2) W1 - 7	60" X 30"	12.50 ♦			
(1) W1 - 8L	18" X 24"	3.00			←
(2) W1 - 8L	36" X 48"	12.00 ♦			
(1) W1 - 8R	18" X 24"	3.00			→
(2) W1 - 8R	36" X 48"	12.00 ♦			
W1-9L	48" X 48"	16.00 ♦			↰
W1-9L	48" X 48"	16.00 ♦			↰
W2-6	36" X 36"	9.00			↻
W3-1a	48" X 48"	16.00 ♦			○
W3-2a	48" X 48"	16.00 ♦			▽
W3-3	48" X 48"	16.00 ♦			◇
W3-5	48" X 48"	16.00 ♦			SPEED REDUCTION
W4-1L	48" X 48"	16.00 ♦			↑
W4-1R	48" X 48"	16.00 ♦			↑
W4-2L	48" X 48"	16.00 ♦			∥
W4-2R	48" X 48"	16.00 ♦			∥
W4-3L	48" X 48"	16.00 ♦			↑
W4-3R	48" X 48"	16.00 ♦			↑
W4-6	48" X 48"	16.00 ♦			↑
W5-1a	48" X 48"	16.00 ♦			PAVEMENT NARROWS
W6-1	48" X 48"	16.00 ♦			↓
W6-2	48" X 48"	16.00 ♦			↓
W6-3	48" X 48"	16.00 ♦			↓
W8-1	48" X 48"	16.00 ♦			BUMP
W8-4	48" X 48"	16.00 ♦			SOFT SHOULDER
W8-6	48" X 48"	16.00 ♦			TRUCK CROSSING

SIGNS REQUIRED (CONT'D)

SIGN NO.	SIZE	UNIT AREA FT²	QUAN. REQ'D.	TOTAL SIGN AREA FT²	REMARKS
W8-7	48" X 48"	16.00 ♦			LOOSE GRAVEL
W8-9	48" X 48"	16.00 ♦			LOW SHOULDER
W8-11	36" X 36"	9.00			UNEVEN LANES
W8-12	48" X 48"	16.00 ♦			NO CENTER STRIPE
(1) W10-1	36" DIA.	7.07			RR
(2) W10-1	48" DIA.	12.56 ♦			
W13-1	24" X 24"	4.00			XX MPH
(1) W14-3	36" X 48" X 48"	5.56			NO PASSING ZONE
(2) W14-3	48" X 64" X 64"	9.89			
W16-2	24" X 18"	3.00			XXX FEET
W19-2	48" X 48"	16.00 ♦			BRIDGE MAY ICE IN COLD WEATHER
(1) W20 - 1	36" X 36"	9.00	4	36.00	ADVANCE ROAD WORK
(2) W20 - 1	36" X 36"	9.00			
W20 - 2	36" X 36"	9.00	2	18.00	ADVANCE DETOUR
W20 - 3	48" X 48"	16.00 ♦			ADVANCE ROAD CLOSED
W20 - 4	48" X 48"	16.00 ♦			ADVANCE ONE-LN. RD.
W20 - 4b	48" X 48"	16.00 ♦			ADVANCE ONE-LN. BR.
W20 - 5L	48" X 48"	16.00 ♦			ADVANCE LT. LN. CLOSED
W20 - 5R	48" X 48"	16.00 ♦			ADVANCE RT. LN. CLOSED
W20 - 7a	48" X 48"	16.00 ♦			
W21 - 1	36" X 36"	9.00			WORKERS
W21 - 1a	36" X 36"	9.00			
W21-2	36" X 36"	9.00			FRESH OIL (TAR)
W21-3	48" X 48"	16.00 ♦			ADVANCE ROAD MACHINERY
W21-5	48" X 48"	16.00 ♦			SHOULDER WORK
W21-6	36" X 36"	16.00 ♦			SURVEY CREW
W24-1L	48" X 48"	16.00 ♦			
W24-1R	48" X 48"	16.00 ♦			
W24-1aL	48" X 48"	16.00 ♦			
W24-1aR	48" X 48"	16.00 ♦			
W24-1bL	48" X 48"	16.00 ♦			
W24-1bR	48" X 48"	16.00 ♦			
VP-IL	12" X 36"	3.00			
VP-IR	12" X 36"	3.00			
[5] OM-3L	12" X 36"	3.00			
[5] OM-3R	12" X 36"	3.00			
D3-1	36" X 12"	3.00	6	18.00	
TOTAL SIGN AREA LESS THAN 10 SQ. FT.					105 SQ. FT.
TOTAL SIGN AREA GREATER THAN 10 SQ. FT. ♦					117 SQ. FT.

NOTES

(1) STANDARD

(2) SPECIAL (USE WHERE WARRANTED)

[1] INTERSTATE ROUTE MARKER

[2] UNITED STATES ROUTE MARKER

[3] STATE ROUTE MARKER

[4] COLORS OF CARDINAL DIRECTION MARKERS AND DIRECTIONAL ARROWS SHALL BE APPROPRIATE TO MATCH ACCOMPANYING ROUTE MARKERS.

[5] BLACK STRIPES ON YELLOW BACKGROUND

[6] INTERSTATE USE ONLY

[7] TOP OF SIGN - BLACK LETTERING ON ORANGE BACKGROUND, BOTTOM OF SIGN - BLACK LETTERING ON WHITE BACKGROUND

THE BACKGROUND OF ALL WARNING SIGNS ("W" SERIES) EXCEPT W10-1 SHALL BE ORANGE. THE W10-1 BACKGROUND SHALL BE YELLOW IN ALL CASES.

KOHL BOOZER LLP
LICENSED PROFESSIONAL ENGINEER
35697
STATE OF MISSISSIPPI
06/26/2026

CITY OF JACKSON

DESIGNED BY: RKB
DETAILED BY: RKB
CHECKED BY: FMT
DATE: 6/26/2026

FMS CON: 109860/701000
PROJECT NO.: STP-7287-00(001)LPA
COUNTY: HINDS

ESTIMATED QUANTITIES

SHEET ID
EQ-3

SHEET NO.
11

PLAN SHEET

6/26/2026 2:07:54 PM EQ.dgn

STANDARD ROADSIDE SIGNS ASSEMBLIES REQUIRED

SHEET NO.	ROAD	LOCATION		STANDARD ROADSIDE SIGNS TO BE MOUNTED	SIZE	THICKNESS	AREA SQ. FT.	AREA BY THICKNESS			STANDARD PIPE		SQUARE TUBE POSTS		NOTES
		STATION						0.080"	0.100"	0.125"	4"	3"	2-P	3-P	
	MCCLUER RD		LT	OM3-L	12"x36"	0.080"	3	3.00					9		PAY FOR AS OM-3L
	MCCLUER RD		RT	OM3-R	12"x36"	0.080"	3	3.00					9		PAY FOR AS OM-3R
	MCCLUER RD		RT	OM3-L	12"x36"	0.080"	3	3.00					9		PAY FOR AS OM-3L
	MCCLUER RD		LT	OM3-R	12"x36"	0.080"	3	3.00					9		PAY FOR AS OM-3R
	MCCLUER RD		RT	W8-13	36"x36"	0.125"	9			9.00			15		
	MCCLUER RD		LT	W8-13	36"x36"	0.125"	9			9.00			15		
TOTAL								**S.F.**	**S.F.**	**S.F.**	**L.F.**	**L.F.**	**L.F.**	**L.F.**	TOTAL EXCLUDES OM-3 SIGNS
								0.0	**0.0**	**18.0**	**0**	**0**	**30**	**0**	

KOHL BOOZER
LICENSED PROFESSIONAL ENGINEER
35697
STATE OF MISSISSIPPI
06/26/2026

CITY OF JACKSON

DESIGNED BY: RKB
DETAILED BY: RKB
CHECKED BY: FMT
DATE: 6/26/2026

FMS CON: 109860/701000
PROJECT NO.: STP-7287-00(001)LPA
COUNTY: HINDS

STANDARD ROADSIDE SIGNS

SHEET ID
SRS-1

SHEET NO.
12


6/26/2026 2:07:54 PM EQ.dgn PLAN SHEET

P.C.M. ELEV. 276.52
PT NAME: 1
N. 996658.5440
E. 2326441.0540
STATION: 7+89.86
OFFSET: 23.74
DESC. 1/2" REBAR

BM ELEV. 275.12
DESC. TYPE=1/2" BOLT

P.C.M. ELEV. 276.97
PT NAME: 3
N. 996823.1130
E. 2326830.3260
STATION: 12+12.41
OFFSET: 15.35
DESC. 1/2" REBAR

0 20 40 60
SCALE: 1" = 20'



EARTHWORK TOTAL THIS SHEET		
Cut	360	Cu.Yds
Fill	10	Cu.Yds
Excess	348	Cu.Yds
Surplus		Cu.Yds
Borrow ( )		Cu.Yds

KOHL BOOZER
LICENSED PROFESSIONAL ENGINEER
35697
STATE OF MISSISSIPPI
06/26/2026

CITY OF JACKSON

DESIGNED BY: RKB
DETAILED BY: RKB
CHECKED BY: FMT
DATE: 6/26/2026


FMS CON: 109860/701000
PROJECT NO.: STP-7287-00(001)LPA
COUNTY: HINDS

PLAN AND PROFILE:
MCCLUER RD.
STA. 9+40 TO STA. 11+40

SHEET ID
WK-3

SHEET NO.
13

PLAN-PROFILE SHEET




6/26/2026 2:07:57 PM WK.dgn

PAVEMENT MARKING			
SYMBOL	DESCRIPTION	UNIT	QUANTITY
①	6" THERMOPLASTIC EDGE STRIPE, CONTINUOUS WHITE	LF	400
②	6" THERMOPLASTIC TRAFFIC STRIPE, SKIP YELLOW	LF	200
③	TWO-WAY YELLOW REFLEC. RAISED MARKER	EACH	6

0 20 40 60

SCALE: 1" = 20'



KOHL BOOZER
LICENSED PROFESSIONAL ENGINEER
35697
STATE OF MISSISSIPPI
06/26/2026

CITY OF JACKSON

DESIGNED BY: RKB
DETAILED BY: RKB
CHECKED BY: FMT
DATE: 6/26/2026

FMS CON: 109860/701000
PROJECT NO.: STP-7287-00(001)LPA
COUNTY: HINDS


PAVEMENT MARKING DETAIL:
MCCLUER RD
STA. 9+40 TO STA. 11+40

SHEET ID
PMD-1

SHEET NO.
14


PLAN SHEET

6/26/2026 2:08:00 PM PMD.dgn




SHEET NO. 15	SHEET ID CS-1	**CONSTRUCTION SIGNING PLAN: MCCLUER RD**	FMS CON: 109860/701000 PROJECT NO.: STP-7287-00(001)LPA COUNTY: HINDS	DESIGNED BY: RKB DETAILED BY: RKB CHECKED BY: FMT DATE: 6/26/2026	**CITY OF JACKSON**

KOHL BOOZER STATE OF MISSISSIPPI 35697 REGISTERED PROFESSIONAL ENGINEER
06/26/2026



SCALE: 1" = 20'



SIGN DETAIL
R1-1 AND R11-2 MOUNTED
ON TYPE III BARRICADE
(SINGLE FACED)

CONSTRUCTION AREA

MAINTAIN TRAFFIC UNDER CONSTRUCTION

KOHL BOOZER
LICENSED PROFESSIONAL ENGINEER
35697
STATE OF MISSISSIPPI
06/26/2026

CITY OF JACKSON

DESIGNED BY: RKB
DETAILED BY: RKB
CHECKED BY: FMT
DATE: 6/26/2026

FMS CON: 109860/701000
PROJECT NO.: STP-7287-00(001)LPA
COUNTY: HINDS

TRAFFIC CONTROL PLAN:
MCCLUER RD

SHEET ID
TC-1

SHEET NO.
16

PLAN SHEET

6/26/2026 2:08:04 PM TCP.dgn

06/26/2026

CITY OF JACKSON

DESIGNED BY: RKB

DETAILED BY: RKB

CHECKED BY: FMT

DATE: 6/26/2026

FMS CON: 109860/701000

PROJECT NO.: STP-7287-00(001)LPA

COUNTY: HINDS

EROSION CONTROL PLAN:
MCCLUER RD.
STA. 9+40 TO STA. 11+40

SHEET ID
ECP-3

SHEET NO.
17

PLAN-PROFILE SHEET

6/26/2026 2:08:06 PM ECP-1.dgn

VEGETATION SCHEDULE

	EROSION CONTROL ITEMS		SEASONAL APPLICATIONS-DATES & RATES				REQUIREMENTS
			SPRING & SUMMER		FALL & WINTER		
	PAY ITEM NO.	ITEMS	RATES	DATES	RATES	DATES	
⑩	211-B001	TOPSOIL FOR SLOPE TREATMENT (LVM)	4" THICK	MARCH 1 TO SEPTEMBER 1	4" THICK	SEPTEMBER 1 TO MARCH 1	TOPSOIL REQUIRED ON SLOPES DETERMINED BY THE ENGINEER DURING CONSTRUCTION.
	225-A001	STANDARD GROUND PREPARATION	PER YD²	MARCH 1 TO SEPTEMBER 1	PER YD²	SEPTEMBER 1 TO MARCH 1	GROUND PREPARATION REQUIRED ON AREAS TO RECEIVE SOLID SODDING OR SEEDING, AS APPLICABLE.
	225-B001	AGRICULTURAL LIMESTONE	1000 LB/ACRE	MARCH 1 TO SEPTEMBER 1		SEPTEMBER 1 TO MARCH 1	LIMESTONE SHALL BE MECHANICALLY SPREAD UNIFORMLY AND INCORPORATED INTO THE SOIL PRIOR TO PLANTING.
	225-A001	COMBINATION FERTILIZER (13-13-13)	250 LB/ACRE	MARCH 1 TO SEPTEMBER 1		SEPTEMBER 1 TO MARCH 1	FERTILIZER SHALL BE MECHANICALLY SPREAD UNIFORMLY AND INCORPORATED INTO THE SOIL PRIOR TO PLANTING.
①	213-C001	SUPERPHOSPHATE	0.5 TONS/ACRE (EST.)	MARCH 1 TO DECEMBER 1			SUPERPHOSPHATE (FOR BID ITEM PURPOSES) .
②	225-A001	SEEDING (BERMUDAGRASS)	80 LB/ACRE	MARCH 1 TO SEPTEMBER 1	20 LB/ACRE	SEPTEMBER 1 TO MARCH 1	SEED REQUIRED ON DISTURBED AREAS. UNHULLED SEED MAY BE REQUIRED DURING THE DORMANT SEASON, AS DIRECTED.
③ ⑬	225-A001	SEEDING (TALL FESCUE)			100 LB/ACRE	NOVEMBER 1 TO APRIL 1	SEED REQUIRED ON DISTURBED AREAS.
③ ⑬	225-A001	SEEDING (CRIMSON CLOVER)			20 LB/ACRE	AUGUST 1 TO APRIL 1	SEED REQUIRED ON DISTURBED AREAS.
	225-A001						
	225-A001						
⑨	225-C001	MULCH - VEGETATIVE MULCH	2 TONS/ACRE (EST.)	MARCH 1 TO SEPTEMBER 1	2 TONS/ACRE (EST.)	SEPTEMBER 1 TO MARCH 1	THE ENGINEER WILL DESIGNATE THE RATES OF APPLICATION (SEE SUBSECTION 215.03.3) .
	216-A001	SOLID SODDING	PER YD²	MARCH 1 TO SEPTEMBER 1	PER YD²	SEPTEMBER 1 TO MARCH 1	SOLID SOD REQUIRED ON AREAS SPECIFIED IN THE CONTRACT OR BY THE ENGINEER.
	219-A001	WATERING	20 GAL/YD² (EST.)	MARCH 1 TO SEPTEMBER 1	20 GAL/YD² (EST.)	SEPTEMBER 1 TO MARCH 1	TO BE USED AS DIRECTED ON THE PLANTING AND ESTABLISHING SOLID SOD.
⑤	220-A001	INSECT PEST CONTROL	PER ACRE		PER ACRE		SEE SECTION 220.
		TEMPORARY EROSION CONTROL ITEMS					
	226-A001	LIGHT GROUND PREPARATION	PER YD²		PER YD²		APPROXIMATELY HALF SQ. YD. STANDARD GROUND PREPARATION.
	226-A001	COMBINATION FERTILIZER (13-13-13)	250 LB/ACRE				QUANTITY BASED ON LIGHT GROUND PREPARATION.
	226-A001	SEEDING (BROWN TOP MILLET)	20 LB/ACRE	APRIL 1 TO AUGUST 31	———	———	QUANTITY BASED ON LIGHT GROUND PREPARATION.
	226-A001	SEEDING (RYE GRASS)	———	———	25 LB/ACRE	SEPTEMBER 1 TO MARCH 31	QUANTITY BASED ON LIGHT GROUND PREPARATION.
	226-A001	SEEDING (OATS)	———	———	90 LB/ACRE	SEPTEMBER 1 TO DECEMBER 15	QUANTITY BASED ON LIGHT GROUND PREPARATION.
	226-A001	VEGETATIVE MATERIAL FOR MULCH	2 TONS/ACRE (EST.)		2 TONS/ACRE (EST.)		QUANTITY BASED ON LIGHT GROUND PREPARATION.

① ALL AREAS THAT HAVE BEEN VEGETATED, UNDER THIS CONTRACT FOR AT LEAST (60) SIXTY DAYS, SHALL RECEIVE ADDITIONAL APPLICATION(S) OF FERTILIZER(S) OF THE TYPE(S) AND RATE(S) OF APPLICATIONS AS DETERMINED BY SOIL TESTS OR AS DIRECTED DURING THE GROWING SEASONS THE CONTRACT IS IN FORCE. GROUND PREPARATION WILL NOT BE REQUIRED FOR THE ADDITIONAL APPLICATIONS. PAYMENT FOR ALL FERTILIZERS ACCEPTABLY APPLIED AS AN ADDITIONAL APPLICATION(S) WILL BE MADE IN ACCORDANCE WITH SUPERPHOSPHATE BID ITEM 213-C001.

② PROPOSAL QUANTITIES ESTIMATED ON THE BASIS THAT 100% OF THE ACREAGE WILL BE SEEDED.

③ PROPOSAL QUANTITIES ESTIMATED ON THE BASIS THAT 50% OF THE ACREAGE WILL BE SEEDED.

④ PROPOSAL QUANTITIES ESTIMATED ON THE BASIS THAT OF THE ACREAGE WILL BE SEEDED.

⑤ QUANTITY ESTIMATED ON THE BASIS THAT 50% OF THE ACREAGE VEGETATED MAY REQUIRE TREATMENT.

⑥ SOW, IN ADDITION TO OTHER SPECIFIED SEEDS, ON HIGH FILL AND BACKSLOPE AREAS SELECTED BY ENGINEERS DURING CONSTRUCTION. PROPOSAL QUANTITIES ESTIMATED ON THE BASIS THAT 50% OF THE ACREAGE WILL BE SEEDED.

⑦ THE ACTUAL RATE/ACRE TO BE DETERMINED BY SOIL TEST DURING CONSTRUCTION.

⑧ BERMUDA GRASS SEED MIX - 50% HOLLED, 50% UNHOLLED.

⑨ BAHIAGRASS WILL NOT BE PERMITTED AS A MULCH MATERIAL.

⑩ PROPOSAL QUANTITIES ESTIMATED ON THE BASIS THAT 75% OF THE ACREAGE SEEDED MAY REQUIRE TOPSOIL.

⑪ PROPOSAL QUANTITIES ESTIMATED ON THE BASIS THAT 50% OF THE ACREAGE SEEDED MAY REQUIRE TOPSOIL.

⑫ THIS ITEM TO BE OMITTED ON AREAS WITHIN 30' FROM EDGE OF PAVEMENT.

⑬ THIS ITEM TO BE OMITTED ON AREAS SELECTED BY THE ENGINEER.

KOHL BOOZER LICENSED PROFESSIONAL ENGINEER 35697 STATE OF MISSISSIPPI
06/26/2026

CITY OF JACKSON

DESIGNED BY: RKB
DETAILED BY: RKB
CHECKED BY: FMT
DATE: 6/26/2026

FMS CON: 109860/701000
PROJECT NO.: STP-7287-00(001)LPA
COUNTY: HINDS


DISTRICT 3 OR 5
VEGETATION SCHEDULE
URBAN - ALL TYPES, EXCLUDING MS DELTA

WK. NO. VS-1

SHEET NO. 18

PLAN SHEET
DATE 2:08:07 PM VS.dgn

SOIL INSTALLATION




SEE OMNI SLEEVE DETAIL

MATERIALS:
PERFORATED SQUARE STEEL TUBE POST AND ANCHOR (PSST): Must be ASTM A1011, Grade 50 steel with an average minimum yield strength after cold-forming must be 60,000 psi. It must be corner welded, scarfed after welding, then zinc coated after scarfing. It must be coated with a chromate conversion coating and a clear organic polymer topcoat. Its interior and exterior will be galvanized. It must have 7/16" holes spaced 1" apart along the centerline of each of its four sides.

POST must be 2" x 14ga x appropriate length.

ANCHOR must be 2-1/4" x 12ga x 36".


OMNI SLEEVE (to be absorbed) must be:
2-1/2" x 12ga x 18" and contain four 4" x 12" x 10ga ASTM A569 steel fins welded to each of the four corner edges of the square sleeve with 4" flat end of each fin positioned 5" down from one end, and must be galvanized. A medium corner bolt must be used to secure the assembly.



OMNI SLEEVE DETAIL

* SIGN POST EXTENDS 5" BELOW TOP OF OMNI SLEEVE

OMNI SLEEVE INSTALLATION
TOP VIEW



KOHL BOOZER LICENSED PROFESSIONAL ENGINEER 35697 STATE OF MISSISSIPPI
06/26/2026

CITY OF JACKSON

DESIGNED BY: RKB
DETAILED BY: RKB
CHECKED BY: FMT
DATE: 6/26/2026

FMS CON: 109860/701000
PROJECT NO.: STP-7287-00(001)LPA
COUNTY: HINDS


SIGN SUPPORT HARDWARE 2.0" SQUARE POST

SHEET ID
SDTSS-1

SHEET NO.
19


PLAN SHEET
6/26/2026 2:08:09 PM SDTSS-1 SIGN SUPPORT HARDWARE 2 INCH SQUARE POST.dgn

STATE	PROJECT NO.
MISS.	



TWO–WAY TRAFFIC
(ASPHALT OR CONCRETE PAVEMENT)

NOTE: THE CRITERIA FOR NO-PASSING ZONES CAN BE FOUND IN THE MDOT ROADWAY DESIGN MANUAL, SECTION 10-1.01.
2



DETAIL "A"



GENERAL NOTES:

* 1. 2" UNLESS SHOWN ELSEWHERE ON THE PLANS. FOR STRIPING ON RUMBLE STRIP SECTIONS REFER TO WK. SHEETS RS-1, RS-2, AND RS-3.


** 2. EDGE STRIPE SHALL BE SAME MATERIAL AS LANE-LINE STRIPE (PAINT OR PLASTIC AS INDICATED IN PAY ITEMS).

*** 3. SPACING OF RETROREFLECTIVE RAISED PAVEMENT MARKERS IS AS FOLLOWS:

	URBAN AREA (ft-in)	RURAL AREA (ft-in)
TANGENT SECTIONS	40'-0"	80'-0"
HORIZONTAL CURVES	40'-0"	40'-0"
INTERCHANGE LIMITS	40'-0"	† 40'-0"

† NOTE: ON THE MAIN FACILITY, RETROREFLECTIVE RED-CLEAR RAISED PAVEMENT MARKERS ON A 40'-0" SPACING WILL BE REQUIRED ON LANE-LINE(S) THROUGH ALL INTERCHANGE AREAS BEGINNING 1000' IN ADVANCE (IN DIRECTION OF TRAFFIC) OF THE EXIT RAMP TAPER AND CONTINUING THROUGH THE INTERCHANGE TO THE END OF THE ENTRANCE RAMP TAPER.

1 4. PAVEMENT MARKERS SHALL BE HIGH PERFORMANCE RETROREFLECTIVE RAISED PAVEMENT MARKERS AS LISTED IN THE MDOT "APPROVED PRODUCTS LIST."



4–LANE WITH ONE–WAY TRAFFIC

DATE	REVISION	BY
4/22/26	UPDATED NOTE	TG
12/11/25	REVISE RPMS AND TEXT	STN

MISSISSIPPI DEPARTMENT OF TRANSPORTATION
ROADWAY DESIGN DIVISION
STANDARD PLAN

PAVEMENT MARKING DETAILS FOR 2–LANE AND 4–LANE DIVIDED ROADWAYS

MDOT MISSISSIPPI DEPARTMENT OF TRANSPORTATION

WORKING NUMBER PM-1

ISSUE DATE: AUGUST 01, 2017

SHEET NUMBER 6051

STATE	PROJECT NO.
MISS.	

GENERAL NOTES:

1. "J-HOOK" CONFIGURATION SILT FENCE APPLICATIONS SHOULD BE USED IN CONJUNCTION WITH PERIMETER SILT FENCE WHEN STORMWATER RUNOFF IS IN TWO DIRECTIONS (DOWN A FILL SLOPE AND DOWN GRADIENT ALONG THE RIGHT-OF-WAY).


2. "SMILE CONFIGURATION" APPLICATIONS SHOULD BE USED AS PERIMETER SILT FENCE WHEN THERE IS ONE-DIRECTIONAL FLOW DOWN A SLOPE.

3. SAND BAGS CAN BE USED AS DIVERSION BERMS TO PREVENT SEDIMENT FROM BEING WASHED ONTO OR ACROSS HARD SURFACES, OR TO HELP SLOW SHEET FLOW VELOCITY WHEN DRAINING AWAY FROM HARD SURFACES.

4. FOR SHORTER SLOPES AND/OR SLOPES THAT ARE LESS STEEP, DIVERSION BERMS CAN BE USED TO SAFELY CONVEY STORMWATER AWAY FROM OR AROUND A DENUDED AREA. THEY CAN BE CONSTRUCTED USING MANUFACTURED SILT DIKE OR BY CONSTRUCTING A TEMPORARY EARTH BERM AND TRENCH WITH GEOTEXTILE OR POLYETHYLENE SHEETING PROTECTION.

5. TEMPORARY DEWATERING STRUCTURES CAN BE USED DURING CULVERT CONSTRUCTION, STREAM DIVERSIONS, OR OTHER CONSTRUCITON ACTIVITIES WHERE TURBID WATERS NEED TO BE CLARIFIED BEFORE RELEASE.

6. THE ABUTMENT SLOPE TOE BERM SHALL BE 3 FT. TALL. THE BERM MAY BE CONSTRUCTED WITH ROCK IN ACCORDANCE WITH REQUIREMENTS FOR ROCK DITCH CHECKS ON WK. NO. ECD-8 OR WITH SOIL IN ACCORDANCE WITH WK. NO. BAS-A. IF BERM IS USED, IT MUST BE GRASSED.




		BY	MISSISSIPPI DEPARTMENT OF TRANSPORTATION ROADWAY DESIGN DIVISION STANDARD PLAN
		REVISION	**TYPICAL TEMPORARY EROSION / SEDIMENT CONTROL APPLICATIONS**
		DATE	ISSUE DATE: AUGUST 01, 2017


WORKING NUMBER ECD-1

SHEET NUMBER 6101


STATE	PROJECT NO.
MISS.	



SEDIMENT BARRIER AT CROSS DRAIN



FRONT ELEVATION




SIDE ELEVATION

TEMPORARY BRUSH BARRIER


NOTES:

1. BRUSH BARRIER MAY BE USED WHERE NATURAL GROUND IS LEVEL OR SLOPING AWAY FROM PROJECT.
2. PLACE BRUSH, LOG AND TREE LAPS APPROXIMATELY PARALLEL TO TOE OF FILL SLOPE WITH SOME OF THE HEAVIER MATERIALS BEING PLACED ON TO TO PROPERLY SECURE THE BARRIER AS DETAILED AT LOCATIONS SHOWN ON PLANS OR AS DIRECTED OR PERMITTED BY THE ENGINEER.
3. TO ALLOW WATER TO SEEP THROUGH BRUSH BARRIER, INTERMINGLE THE BRUSH, LOG AND TREE LAPS SO AS NOT TO FORM A SOLID DAM.
4. THE BRUSH BARRIER MAY BE CHOKED WITH FILTER FABRIC. THE COST OF FABRIC TO BE INCLUDED IN OTHER ITEMS BID.
5. TEMPORARY BRUSH BARRIER WILL NOT BE MEASURED FOR SEPARATE PAYMENT.

NOTE: ANCHOR AND INSTALL SILT FENCE PER DETAILS SHOWN ON WK. NO. ECD-3




"J–HOOK" SILT FENCE
APPLICATION



NOTE:
1. EL.(A) = EL.(B) TO MAXIMIZE STORAGE.

"SMILE–CONFIGURATION" SILT FENCE
APPLICATION




- SILT FENCE SHOULD BE LOCATED AWAY FROM THE TOE OF THE SLOPE TO PROVIDE SUFFICIENT SPACE TO ALLOW A BROAD, FLAT AREA FOR SEDIMENT ACCUMULATION AND MAINTENANCE ACTIVITIES. THE ENDS OF THE SILT FENCE SHOULD BE TURNED UP GRADIENT TO MAXIMIZE STORAGE.


SILT FENCE SECTION AT
TOE OF FILL

BY	MISSISSIPPI DEPARTMENT OF TRANSPORTATION ROADWAY DESIGN DIVISION STANDARD PLAN	
REVISION	**DETAILS OF SEDIMENT BARRIER APPLICATIONS**	WORKING NUMBER ECD-2
DATE	ISSUE DATE: AUGUST 01, 2017	SHEET NUMBER 6102

STATE	PROJECT NO.
MISS.	




ELEVATION VIEW



METHOD I

METHOD II
MECHANICAL INSTALLATION

SIDE VIEW



PLAN VIEW

REQUIRED LAPPING

GENERAL NOTES:

1. SILT FENCES SHOULD BE USED IN AREAS WHERE FLOW IS NOT SEVERE.
2. SILT FENCES ARE TEMPORARY SEDIMENT CONTROL ITEMS THAT SHOULD BE ERECTED OPPOSITE ERODIBLE AREAS SUCH AS NEWLY GRADED FILL SLOPES AND ADJACENT TO STEAMS AND CHANNELS.
3. SILT FENCE SHOULD BE PLACED WELL INSIDE RIGHT-OF-WAY AND ALONG EDGE OF CLEARING LIMITS. THIS WILL ALLOW ROOM FOR BACK-UP FENCE IF FIRST FENCE BECOMES FULL.
4. WHENEVER POSSIBLE SILT FENCE SHOULD BE CONSTRUCTED ACROSS A LEVEL AREA IN THE SHAPE OF A SMILE. THIS AIDS IN PONDING OF RUNOFF AN FACILITATES SEDIMENTATION.
5. THE CONTRACTOR MAY ELECT TO USE EITHER METHOD I OR METHOD II. COST TO BE LINEAR FEET OF SILT FENCE.
6. METHOD II INSTALLATION SHALL BE ACCOMPLISHED USING AN IMPLEMENT THAT IS MANUFACTURED FOR THE APPLICATION AND PROVIDES A CONFIGURATION MEETING THE REQUIREMENTS OF DETAIL.
7. WIRE SHALL BE A MINIMUM OF 32" IN WIDTH AND SHALL HAVE A MINIMUM OF 6 LINE WIRES WITH 12" STAY SPACING.
8. GEOTEXTILE FABRIC MEETING THE TYPE II MATERIAL REQUIREMENTS AND INSTALLED ACCORDING TO SPECIFICATION MAY BE USED WITHOUT WIRE FENCE.

BY	REVISION	DATE

MISSISSIPPI DEPARTMENT OF TRANSPORTATION
ROADWAY DESIGN DIVISION
STANDARD PLAN

DETAILS OF SILT FENCE INSTALLATION


MDOT

WORKING NUMBER
ECD-3

ISSUE DATE: AUGUST 01, 2017

SHEET NUMBER
6103

STATE	PROJECT NO.
MISS.	



EXAMPLE: HEIGHT OF STRUCTURE 1.5′
GRADE 1%
EXTEND VERTICALLY FROM 1.5′ HEIGHT TO INTERSECT S = 1.0% GRADE
EXTEND 90° TO THE LEFT TO DETERMINE SPACING (150′+)

DITCH CHECK SPACING

GENERAL NOTES:

1. THE DITCH CHECK PERSPECTIVE ILLUSTRATES A TOOL BOX OF TEMPORARY PRACTICES THAT MAY BE USED. DITCH CHECKS ARE INSTALLED TO CONTROL RUNOFF VELOCITY AND THUS REDUCE EROSION AND PROVIDE FOR TRAPPING OF SEDIMENTS.
2. SELECTION OF THE APPROPRIATE DITCH CHECK SHOULD BE A FUNCTION OF CONSTRUCTION PHASE, DRAINAGE AREA, DITCH GRADIENT, SOIL TYPE, ECONOMY AND SAFETY.
3. DITCH CHECKS CAN BE REMOVED FOR MAINTENANCE AND/OR REPLACEMENT BUT MUST REMAIN IN PLACE UNTIL UPSLOPE AREAS HAVE BEEN PERMANENTLY STABILIZED. MAINTENANCE INCLUDES REMOVAL OF SEDIMENT BEGINNING WHEN SEDIMENT ACCUMULATION REACHES ⅓ THE CAPACITY OR HEIGHT OF THE STRUCTURE AND NEVER ALLOWING FOR SEDIMENT TO ACCUMULATE MORE THAN ½ THE VOLUME OR HEIGHT OF THE DITCH CHECK STRUCTURE.
4. HAY BALES SHOULD BE USED TO INTERCEPT LOW VOLUME FLOWS IN LOW TO MODERATE GRADIENT DITCHES.
5. SILT FENCE DITCH CHECKS SHOULD BE USED WHERE IT HAS BEEN DETERMINED THAT HAY BALE CHECKS ARE INADEQUATE. SILT FENCE DITCH CHECKS SHOULD BE USED TO INTERCEPT LOW VOLUME FLOWS IN LOW TO MODERATE GRADIENT DITCHES.
6. SANDBAG DITCH CHECKS SHOULD BE USED FOR VELOCITY REDUCTION AND MINIMAL SEDIMENT TRAPPING IN CONCRETE PAVED DITCHES OR IN DITCHES THAT HAVE ROCK BOTTOMS.
7. WATTLE DITCH CHECKS CAN BE USED FOR VELOCITY REDUCTION AND CONTROL OF SEDIMENT TRANSPORT UNDER LOW TO MEDIUM FLOW CONDITIONS.
8. SILT DIKES CAN BE USED IN DITCHES WITH CONCENTRATED FLOWS WITHIN THE CLEAR ZONE WHERE RIPRAP CAN NOT BE USED. AS CONSTRUCTION PROGRESSES.
9. ROCK DITCH CHECKS WITH SUMP EXCAVATION CAN BE PLACED IN DITCHES TO ASSURE ON-SITE SEDIMENT TRAPPING REQUIREMENTS ARE MET. DITCH CHECK WITH SUMP EXCAVATION IS USED WHEN DITCHES RECEIVE DRAINAGE FROM CUT OR FILL SLOPES OR OTHER CRITICAL AREAS WHERE SOIL EROSION IS EXPECTED. DRAINAGE AREA FOR A TEMPORARY SEDIMENT TRAP SHOULD BE LIMITED TO 3 ACRES. THEY CAN BE USED IN SERIES TO INCREASE ON-SITE SEDIMENT TRAPPING EFFICIENCY.
10. DITCH CHECKS, IN NO CASE, SHALL BE PLACED IN LIVE STREAMS.
11. CONFIGURATION AND SPACING MAY BE ADJUSTED IF APPROVED BY THE ENGINEER TO ACCOMMODATE TRAVELWAY SAFETY, WATER FLOW, OR SOIL AND INSTALLATION CHALLENGES.

DATE	REVISION	BY

MISSISSIPPI DEPARTMENT OF TRANSPORTATION
ROADWAY DESIGN DIVISION
STANDARD PLAN

DITCH CHECK STRUCTURES, TYPICAL APPLICATIONS AND DETAILS


MDOT

WORKING NUMBER
ECD-4

ISSUE DATE: AUGUST 01, 2017

SHEET NUMBER
6104


STATE	PROJECT NO.
MISS.	




PLAN VIEW

NOTES:


1. ANCHOR AND INSTALL PER DETAILS FOR SILT FENCE SPACING GUIDELINES ON WK. NO. ECD-4.
2. A "W" SHAPE MAY BE USED FOR WIDER DITCHES.



SECTION A–A



PLAN VIEW
TRAPEZOIDAL DITCH



PROFILE VIEW
TRAPEZOIDAL DITCH

NOTES:

1. SILT FENCE DITCH CHECKS SHOULD BE USED WHERE IT HAS BEEN DETERMINED THAT HAY BALE CHECKS ARE INADEQUATE. SILT FENCE DITCH CHECKS SHOULD BE USED TO INTERCEPT LOW VOLUME FLOWS IN LOW TO MODERATE GRADIENT DITCHES.
2. HAY BALES SHOULD BE USED TO INTERCEPT LOW VOLUME FLOWS IN LOW TO MODERATE GRADIENT DITCHES.
3. MINIMUM RECOMMENDED CHECK SPACING IS 100 FEET UNLESS SHOWN OTHERWISE ON THE PLANS OR EROSION CONTROL PLAN APPROVED BY THE ENGINEER. SEE SPACING GUIDANCE ON WK. NO. ECD-4.
4. ANCHORING WOOD STAKES SHALL BE SIZED, SPACED, AND BE OF A MATERIAL THAT EFFECTIVELY SECURES THE CHECK. A MINIMUM OF TWO STAKES PER BALE IS REQUIRED. ALL NON-DEGRADABLE MATERIALS SHALL BE REMOVED WHEN NO LONGER NEEDED.
5. BALES SHALL BE EMBEDDED IN THE SOIL A MINIMUM OF 3 INCHES.
6. BALES SHALL BE PLACED IN A ROW WITH ENDS TIGHTLY ABUTTING THE ADJACENT BALES. THE BALES SHALL BE PLACED WITH BINDINGS PARALLEL TO THE GROUND.
7. SOIL IS COMPACTED ALONG THE BASE OF THE UPSTREAM FACE TO PREVENT PIPING.
8. MULTIPLE ADJACENT ROWS OF BALES ARE REQUIRED AS SHOWN.

DATE	REVISION	BY

MISSISSIPPI DEPARTMENT OF TRANSPORTATION
ROADWAY DESIGN DIVISION
STANDARD PLAN

TEMPORARY EROSION, SEDIMENT, AND WATER POLLUTION CONTROL MEASURES


(SILT FENCE AND HAY BALE DITCH CHECKS)

WORKING NUMBER ECD-5


ISSUE DATE: AUGUST 01, 2017

SHEET NUMBER 6105


STATE	PROJECT NO.
MISS.	



DETAIL (DITCH CHECK)



ELEVATION DETAIL



SECTION A–A

NOTES:

1. WATTLE DITCH CHECKS CAN BE USED FOR VELOCITY REDUCTION AND CONTROL OF SEDIMENT TRANSPORT UNDER LOW TO MEDIUM FLOW CONDITIONS.
2. THE PLACEMENT INTERVAL BETWEEN WATTLE DITCH CHECK SHALL BE 100' UNLESS SHOWN OTHERWISE ON THE PLANS OR EROSION CONTROL PLAN APPROVED BY THE ENGINEER. SEE SPACING GUIDANCE ON WK. NO. ECD-4.
3. ANCHORING WOOD STAKES SHALL BE SIZED, SPACED, DRIVEN, AND BE OF A MATERIAL THAT EFFECTIVELY SECURES THE CHECK. STAKE SPACING SHALL BE A MAXIMUM OF THREE FEET. ALL NON-DEGRADABLE MATERIALS SHALL BE REMOVED WHEN NO LONGER NEEDED.
4. TRENCHING OF WATTLES MAY BE NECESSARY IF PIPING BECOMES EVIDENT.
5. WATTLES SHOULD NOT BE USED IN HARD BOTTOM CHANNELS.
6. IN THE EVENT WATTLES CANNOT BE SECURED IN PLACE USING WOOD STAKES, SAND BAGS MAY BE USED IN LIEU OF WOOD STAKES IN ORDER TO SECURE THE WATTLES IN PLACE. IF SANDS BAGS ARE USED IN THIS APPLICATION THEY WILL NOT BE A SEPARATE PAY ITEM.

	BY	REVISION	DATE

MISSISSIPPI DEPARTMENT OF TRANSPORTATION
ROADWAY DESIGN DIVISION
STANDARD PLAN

DETAILS OF EROSION CONTROL WATTLE DITCH CHECK


MDOT

WORKING NUMBER
ECD-6

ISSUE DATE: AUGUST 01, 2017


SHEET NUMBER
6106

STATE	PROJECT NO.
MISS.	




NOTES:

PLAN VIEW



POINT "A" SHALL BE HIGHER THAN POINT "B" TO ENSURE THAT WATER FLOWS OVER THE DIKE AND NOT AROUND THE ENDS

SECTION B–B



SECTION A–A

NOTE: STAPLES SHALL BE PLACED WHERE THE UNITS OVERLAP AND IN THE CENTER OF THE UNIT

SILT DIKE INSTALLATION FOR ROADWAY DITCHES

NOTES:

1. SILT DIKES CAN BE USED IN DITCHES WITH CONCENTRATED FLOWS WITHIN THE CLEAR ZONE WHERE RIPRAP CANNOT BE USED.

2. SILT DIKES MAY ALSO BE USED:

   A. IN AREAS WHERE CONSTRUCTION TRAFFIC TRAVELS (AS SHOWN ON WK. NO. ECD-16), PROVIDED THE SILT DIKE REBOUNDS TO ITS ORIGINAL SHAPE. SILT DIKES WHICH DO NOT REBOUND TO THEIR ORIGINAL SHAPE SHALL BE REPLACED BY THE CONTRACTOR AT NO ADDITIONAL EXPENSE TO THE DEPARTMENT.

   B. AT THE ENDS OF AND ALONG THE EDGES OF CONSTRUCTION ROADS THAT CROSS THE WATERS OF THE U.S. (AS SHOWN ON WK. NO. ECD-17).

3. THE PLACEMENT INTERVAL BETWEEN SILT DIKE DITCH CHECK SHALL BE 100' UNLESS SHOWN OTHERWISE ON THE PLANS OR EROSION CONTROL PLAN APPROVED BY THE ENGINEER. SEE SPACING GUIDANCE ON WK. NO. ECD-4.

4. INSTALLATION SHALL BE IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS.

5. THE TRIANGULAR SILT DIKE SHAPE IS ONLY SHOWN FOR DEPICTION PURPOSES. OTHER SHAPED SILT DIKES MAY BE USED.

6. WHEN THE SILT DIKE, USED AS A DITCH CHECK, IS MANUFACTURED WITH AN APRON ON ONE SIDE ONLY, THE SILT DIKE SHALL BE INSTALLED AS SHOWN IN SECTION A-A. THE APRON SHALL BE INSTALLED ON THE UPSTREAM SIDE AND TYPE V NON-WOVEN GEOTEXTILE FABRIC INSTALLED ON THE DOWNSTREAM SIDE.

7. THE COST OF THE FABRIC SHALL BE INCLUDED IN OTHER ITEMS BID.

REVISION	BY	DATE

MISSISSIPPI DEPARTMENT OF TRANSPORTATION
ROADWAY DESIGN DIVISION
STANDARD PLAN

DETAILS OF EROSION CONTROL SILT DIKE DITCH CHECK


MDOT

WORKING NUMBER
ECD-7

ISSUE DATE: AUGUST 01, 2017


SHEET NUMBER
6107

STATE	PROJECT NO.
MISS.	




PLAN VIEW

DETAIL FOR TRAPEZOIDAL DITCH




SECTION B–B



SECTION A–A

TEMPORARY ROCK DITCH CHECKS IN ROADSIDE DITCHES



DETAIL FOR SPACING BETWEEN DITCH CHECKS

NOTES:

1. ROCK DITCH CHECKS SHOULD ONLY BE USED FOR REDUCING THE VELOCITY OF FLOWING WATER.
2. MINIMUM SPACING FOR ROCK DITCH CHECKS IS 100 FEET UNLESS OTHERWISE SHOWN ON THE PLANS OR EROSION CONTROL PLAN APPROVED BY THE ENGINEER. SEE SPACING GUIDANCE ON WK. NO. ECD-4.
3. ROCK DITCH CHECKS SHOULD ONLY BE USED UP-GRADIENT OF AND ALONG WITH ADDITIONAL DOWN-GRADIENT SEDIMENT CONTROL BEST MANAGEMENT PRACTICES (BMP'S).
4. THE COST OF FABRIC SHALL BE INCLUDED IN OTHER ITEMS BID.

BY	REVISION	DATE

MISSISSIPPI DEPARTMENT OF TRANSPORTATION
ROADWAY DESIGN DIVISION
STANDARD PLAN

ROCK DITCH CHECK


MDOT
MISSISSIPPI DEPARTMENT OF TRANSPORTATION

WORKING NUMBER
ECD-8

ISSUE DATE: AUGUST 01, 2017


SHEET NUMBER
6108

STATE	PROJECT NO.
MISS.	




PLAN VIEW

DETAIL FOR TRAPEZOIDAL DITCH




PLAN VIEW


DETAIL FOR USE OTHER THAN DITCH



SECTION B–B



SECTION C–C



SECTION A–A

TEMPORARY ROCK DITCH CHECKS IN ROADSIDE DITCHES

GENERAL NOTES:

1. ROCK FILTER DAMS (RFD) MAY BE USED AS A DISCHARGE STRUCTURE WHILE WORKING WITH HIGHLY EROSIVE SOIL. RFD'S MAY BE USED AS PART OF A "BMP TRAIN" AND MAY BE USED IN SUCCESSION AT A MINIMUM SPACING OF 100 FT. OR PER THE EROSION CONTROL PLAN APPROVED BY THE ENGINEER.

2. THE COST OF THE FABRIC SHALL BE INCLUDED IN OTHER ITEMS BID.

BY	REVISION	DATE

MISSISSIPPI DEPARTMENT OF TRANSPORTATION
ROADWAY DESIGN DIVISION
STANDARD PLAN

ROCK FILTER DAM


MDOT MISSISSIPPI DEPARTMENT OF TRANSPORTATION

WORKING NUMBER
ECD-9


ISSUE DATE: AUGUST 01, 2017

SHEET NUMBER
6109


STATE	PROJECT NO.
MISS.	



PLAN VIEW



SECTION A–A



PROFILE VIEW

NOTES:

1. ROCK DITCH CHECKS WITH SUMP EXCAVATION CAN BE PLACED IN DITCHES TO ASSURE ON-SITE SEDIMENT TRAPPING REQUIREMENTS ARE MET. DITCH CHECK WITH SUMP EXCAVATION IS USED WHEN DITCHES RECEIVE DRAINAGE FROM CUT OR FILL SLOPES OR OTHER CRITICAL AREAS WHERE SOIL EROSION IS EXPECTED. DRAINAGE AREA FOR A TEMPORARY SEDIMENT TRAP SHOULD BE LIMITED TO 3 ACRES. THEY CAN BE USED IN SERIES TO INCREASE ON-SITE SEDIMENT TRAPPING EFFICIENCY.

2. THE COST OF THE FABRIC SHALL BE INCLUDED IN OTHER ITEMS BID.

BY	REVISION	DATE

MISSISSIPPI DEPARTMENT OF TRANSPORTATION
ROADWAY DESIGN DIVISION
STANDARD PLAN

ROCK DITCH CHECK WITH SUMP EXCAVATION AND ROCK FILTER DAM


MDOT MISSISSIPPI DEPARTMENT OF TRANSPORTATION

WORKING NUMBER
ECD-10

ISSUE DATE: AUGUST 01, 2017

SHEET NUMBER
6110


STATE	PROJECT NO.
MISS.	



DETAIL (DITCH CHECK)


GENERAL NOTES:

1. SANDBAG DITCH CHECKS ARE USED FOR VELOCITY REDUCTION AND MINIMAL SEDIMENT TRAPPING IN CONCRETE PAVED DITCHES OR IN DITCHES WITH ROCKY BOTTOMS.
2. MINIMUM RECOMMENDED PLACEMENT INTERVAL BETWEEN SANDBAG DITCH CHECK IS 100′ UNLESS SHOWN OTHERWISE ON THE PLANS OR APPROVED BY THE ENGINEER. SEE SPACING GUIDANCE ON WK. NO. ECD-4.
3. PREVENTING SEDIMENT FROM ENTERING A PAVED DITCH IS PREFERABLE TO CAPTURING SEDIMENT WITHIN PAVED DITCH.
4. ROCKBAGS MAY BE USED IN LIEU OF SANDBAGS, ONLY WHEN PAY ITEM FOR ROCKBAGS IS INCLUDED IN THE CONTRACT.



SECTION A–A

(IN DITCH BOTTOM)



ELEVATION DETAIL


		BY	MISSISSIPPI DEPARTMENT OF TRANSPORTATION ROADWAY DESIGN DIVISION STANDARD PLAN
		REVISION	**DETAILS OF EROSION CONTROL SANDBAG DITCH CHECK**
		DATE	ISSUE DATE: AUGUST 01, 2017

MDOT


WORKING NUMBER
ECD-21

SHEET NUMBER
6121


STATE	PROJECT NO.
MISS.	




ELEVATION VIEW




SIDE VIEW
SECTION A–A
METHOD I



SIDE VIEW
SECTION A–A
METHOD II
MECHANICAL INSTALLATION



PLAN VIEW
REQUIRED LAPPING



DETAIL A

GENERAL NOTES:

1. RETENTION BARRIERS SHOULD BE USED IN AREAS WHERE FLOW IS NOT SEVERE.
2. RETENTION BARRIERS ARE TEMPORARY SEDIMENT CONTROL ITEMS THAT SHOULD BE ERECTED OPPOSITE ERODIBLE AREAS SUCH AS NEWLY GRADED FILL SLOPES AND ADJACENT TO STREAMS AND CHANNELS.
3. RETENTION BARRIERS SHOULD BE PLACED WELL INSIDE RIGHT-OF-WAY AND ALONG EDGE OF CLEARING LIMITS. THIS WILL ALLOW ROOM FOR A BACK-UP FENCE IF FIRST FENCE BECOMES FULL.
4. THE CONTRACTOR MAY ELECT TO USE EITHER METHOD I OR METHOD II. COST TO BE LINEAR FEET OF SEDIMENT RETENTION BARRIER.
5. METHOD II INSTALLATION SHALL BE ACCOMPLISHED USING AN IMPLEMENT THAT IS MANUFACTURED FOR THE APPLICATION AND PROVIDES CONFIGURATION MEETING THE REQUIREMENTS OF THE DETAIL.
6. WIRE SHALL BE MINIMUM OF 32" IN WIDTH AND SHALL HAVE A MINIMUM OF 6 LINE WIRES WITH 12" STAY SPACING.
7. GEOTEXTILE FABRIC MEETING THE TYPE II MATERIAL REQUIREMENTS AND INSTALLED ACCORDING TO SPECIFICATION MAY BE USED WITHOUT WIRE FENCE.

BY	REVISION	DATE

MISSISSIPPI DEPARTMENT OF TRANSPORTATION
ROADWAY DESIGN DIVISION
STANDARD PLAN

SEDIMENT RETENTION BARRIER


MDOT

WORKING NUMBER
ECD-22


ISSUE DATE: AUGUST 01, 2017

SHEET NUMBER
6122


STATE	PROJECT NO.
MISS.	




"V" TYPE SECTION



FLAT BOTTOM SECTION



DETAIL OF CONSTRUCTION JOINT



DETAIL OF TOE WALL


NOTE: TOE WALL REQUIRED UPSTREAM AND DOWNSTREAM.

CONCRETE PAVED DITCH

NOTES:


1. CONCRETE PAVED DITCHES SHALL BE GROOVED AT 20'-0" INTERVALS. THE GROOVES SHALL BE CUT TO A DEPTH OF NOT LESS THAN 1".
2. DIMENSIONS D & W ARE AS FOLLOWS:
   D(MINIMUM) = 6"
   D(NOMINAL) = 9"
   W(MINIMUM) = 24"
3. CHAIR SUPPORTS FOR THE WIRE MESH WILL NOT BE REQUIRED. HOWEVER, THE CONTRACTOR SHALL PLACE THE WIRE MESH IN A SATISFACTORY AND WORKMANLIKE MANNER TO ENSURE THAT THE FINAL POSITION IS REASONABLY NEAR THE POSITION INDICATED.

*4. CENTER ROW OF STAPLES MAY BE OMITTED ON DITCH LINER.




ANCHOR TRENCH DETAIL

NOTE: ANCHOR TRENCH REQUIRED AT THE BEGINNING AND ENDING OF EACH AREA TO BE COVERED, EXCEPT DOWNSTREAM END ADJOINING A STRUCTURE.




PLAN




SECTION

DITCH LINER TREATMENT
(EXCELSIOR BLANKET, JUTE MESH OR EROSION CONTROL FABRIC)

NOTE: DITCHES TREATED WITH DITCH LINER WILL BE VEGETATED PRIOR TO TREATMENT, UNLESS OTHERWISE INDICATED.



FLAT BOTTOM SECTION




"V" TYPE SECTION

RIPRAP TREATMENT


NOTES:

1. DIMENSIONS D, W AND X ARE VARIABLE AND ARE SHOWN ELSEWHERE ON THE PLANS.
2. THE RIPRAP SIZE AND MINIMUM DEPTH "H" FOR RIPRAP TREATMENT ARE AS FOLLOWS.

RIPRAP SIZE & MINIMUM DEPTH "H"	
H (in)	RIPRAP SIZE (lbs)
12"	100
18"	300



SOLID SOD TREATMENT



NOTE: SOLID SOD (STRIPS OR BLOCKS) SHOULD BE STAPLED, PINNED, PEGGED OR STAKED AT THE FOUR CORNERS OR AT THE MAXIMUM SPECIFIED SPACING.

GENERAL NOTE:

1. FOR LOCATION OF APPROPRIATE DITCH TREATMENTS, SEE PLAN SHEETS AS DENOTED BY THE FOLLOWING LEGEND OR AS DIRECTED BY THE ENGINEER:

DITCH LINER
SOLID SOD
CONCRETE PAVED DITCH
RIPRAP

BY	REVISION	DATE

MISSISSIPPI DEPARTMENT OF TRANSPORTATION
ROADWAY DESIGN DIVISION
STANDARD PLAN

DETAILS OF TYPICAL DITCH TREATMENTS


MDOT MISSISSIPPI DEPARTMENT OF TRANSPORTATION

WORKING NUMBER DT-1

ISSUE DATE: AUGUST 01, 2017


SHEET NUMBER 6123

STATE	PROJECT NO.
MISS.	



ELEVATION FROM ℄ ROADWAY


✱✱ NOTE: OPTIONAL BEAM LENGTHS.




SINGLE–FACED BARRIER DOUBLE–FACED BARRIER

SECTION A–A


✱ NOTE: UNLESS SPECIFIED OTHERWISE ON THE PLANS.



TYPICAL GUARDRAIL SECTION



ELEVATION




SECTION


GUARDRAIL SPLICE DETAIL

GENERAL NOTES:

1. GUARDRAIL SHALL MEET THE REQUIREMENTS OF AASHTO M 180, CLASS A, TYPE 1 UNLESS OTHERWISE DESIGNATED.
2. GUARDRAIL SHALL BE SINGLE FACED UNLESS OTHERWISE DESIGNATED.
3. GUARDRAIL SECTIONS SHALL BE LAPPED IN THE DIRECTION OF TRAFFIC FLOW FOR THE LANE NEAREST THE GUARDRAIL. THE ONLY EXCEPTION NOTED IS THAT GUARDRAIL SHALL BE LAPPED FOR APPROACHING TRAFFIC ON A BRIDGE WITH 2-WAY TRAFFIC.
4. STEEL POSTS SHALL CONFORM TO ASTM A36 (EXCEPT ULTRASONIC TESTING). THEY SHALL BE GALVANIZED IN ACCORDANCE WITH AASHTO M 111 EXCEPT WHEN CORROSION RESISTANT STEEL IS REQUIRED IN WHICH CASE POSTS SHALL CONFORM TO AASHTO SPECIFICATIONS FOR CORROSION RESISTANCE AND SHALL NOT BE PAINTED OR GALVANIZED. NO PUNCHING, DRILLING OR CUTTING WILL BE PERMITTED AFTER GALVANIZING EXCEPT FOR HOLES TO MOUNT GUARDRAIL DELINEATORS.
5. ALL MODIFIED WOOD BLOCKOUTS SHALL BE TREATED TIMBER IN ACCORDANCE WITH MISSISSIPPI DEPARTMENT OF TRANSPORTATION STANDARD SPECIFICATIONS.
6. FOR OTHER DETAILS OF POSTS, POST ACCESSORIES, FASTENERS & RAIL ELEMENTS, SEE AASHTO-AGC-ARTBA JOINT TASK FORCE NO. 13, TITLED "A GUIDE TO STANDARDIZED HIGHWAY BARRIER HARDWARE," LATEST EDITION.




GUARDRAIL BOLT



RECESSED NUT

GUARDRAIL BOLTS		
BOLT	L	T (MIN.)
"A"	1¼"	1"
"B"	12"	4"
"C"	14"	4"




HEX NUT AND BOLT "F"

NOTES:

1. ALL GUARDRAIL BOLTS ARE ⅝" - 11 UNC THREAD PITCH.
2. IF ANY BOLT EXTENDS MORE THAN ¼" FROM THE NUT, THE BOLT SHOULD BE TRIMMED BACK.

FASTENER DETAILS



DETAILS OF ADJUSTABLE HEIGHT BLOCKOUT ASSEMBLY

NOTES:

1. ON INITIAL INSTALLATION, THE MODIFIED WOOD BLOCKOUT SHALL BE FASTENED TO THE BOTTOM HOLE IN THE STEEL POST. OTHER HOLES IN THE STEEL POST AND THE MODIFIED WOOD BLOCKOUT ARE FOR FUTURE 2" HEIGHT ADJUSTMENTS WHEN THE ROADWAY IS RESURFACED.
2. AN ADDITIONAL GUARDRAIL BOLT "C" AND RECESSED NUT IS REQUIRED FOR THE SECOND HEIGHT ADJUSTMENT.
3. HOLE DETAILS ARE REQUIRED ON ALL STEEL POSTS AND MODIFIED WOOD BLOCKOUTS.
4. STEEL POSTS ARE FABRICATED FROM W6 X 9 STRUCTURAL STEEL SHAPES.
5. MODIFIED WOOD BLOCKOUTS ARE FABRICATED FROM 6" X 12" TREATED TIMBER UNLESS SPECIFIED OTHERWISE ON THE PLANS.
6. ALL HOLES IN BOTH STEEL POSTS AND MODIFIED WOOD BLOCKOUTS ARE ¾" IN DIAMETER.

DATE	REVISION	BY

MISSISSIPPI DEPARTMENT OF TRANSPORTATION
ROADWAY DESIGN DIVISION
STANDARD PLAN

GUARDRAIL: "W" BEAM (STEEL POSTS)


MDOT MISSISSIPPI DEPARTMENT OF TRANSPORTING

WORKING NUMBER GR-1B

ISSUE DATE: AUGUST 01, 2017


SHEET NUMBER 6203

STATE	PROJECT NO.
MISS.	




TYPE "1" "W" BEAM END SECTION

NOTE: THE TYPE "1" END SECTION IS THE STANDARD FLARED "W" BEAM END SECTION AND IS USED WITH THE TYPE "A" AND TYPE "E" BRIDGE END SECTIONS. THE CROSS-SECTIONAL DIMENSIONS OF THIS PART ARE IDENTICAL TO THOSE OF THE STANDARD "W" BEAM GUARDRAIL.




TYPE "2" "W" BEAM END SECTION

NOTE: THE TYPE "2" END SECTION IS A MODIFICATION OF THE STANDARD ROUNDED "W" BEAM END SECTION AND IS USED EXCLUSIVELY WITH THE TYPE "C" BRIDGE END SECTION. THE CROSS-SECTIONAL DIMENSIONS OF THIS PART ARE IDENTICAL TO THOSE OF THE STANDARD "W" BEAM GUARDRAIL.




PLAN OF BRIDGE END SECTION





SECTION A–A

*NOTE: UNLESS OTHERWISE SPECIFIED ON THE PLANS.




DETAIL OF PLATE "B"






DETAIL OF PLATE "Z"





HIGH-STRENGTH STRUCTURAL HEX NUT AND BOLT "D"


(ASTM A 325)




FASTENER DETAILS











GUARDRAIL CONNECTION AT BRIDGE END





GUARDRAIL CONNECTION DETAILS

NOTE: UNLESS OTHERWISE SPECIFIED, THE BLOCKOUT ASSEMBLY, FASTENER AND PLATE DETAILS SHOWN ABOVE ARE ALSO APPLICABLE TO THE TYPE "E" BRIDGE END SECTION. SEE GENERAL NOTE 3.

GENERAL NOTES:

1. ALL NOTES AND DETAILS PERTAINING TO NORMAL "W" BEAM GUARDRAIL INSTALLATION NOT SPECIFICALLY MODIFIED ON THIS SHEET WILL BE FOUND ON EITHER SHEET GR-1 (WOOD POSTS) OR GR-1B (STEEL POSTS).
2. WOOD POSTS ARE SHOWN ON THIS SHEET. WHEN STEEL POSTS ARE INSTALLED, A SOIL BEARING PLATE IS PLACED ON THE STANDARD SIZE STEEL POST FOR POSTS 1 THRU 3 AND A RECTANGULAR GUARDRAIL PLATE WASHER IS PLACED UNDER THE STANDARD POST BOLT HEAD FOR POSTS 1 THRU 6. SEE DETAILS FOR STEEL POST INSTALLATIONS ON SHEET GR-1B.
3. FOR INFORMATION PERTAINING TO THE INSTALLATION OF THE TYPE "E" BRIDGE END SECTION, SEE SHEET GR-2A.
4. THE HEIGHT OF RAIL AT THE BRIDGE END IS 20⅞" AND WILL BE TRANSITIONED TO 25" AT POST 7.
5. ALL GUARDRAIL ELEMENTS SHALL BE LAPPED IN THE DIRECTION OF TRAFFIC.
6. POINT "a", WHICH IS AT THE CENTERLINE BETWEEN THE ANCHOR BOLTS, WILL BE CENTERED OVER THE CENTERLINE OF THE BRIDGE END WALL EXCEPT IN SKEWED BRIDGE ENDS WHERE THE BOLT NEAREST THE JOINT WILL BE A MINIMUM OF 3" FROM THE JOINT.

MISSISSIPPI DEPARTMENT OF TRANSPORTATION
ROADWAY DESIGN DIVISION
STANDARD PLAN

GUARDRAIL: BRIDGE END SECTIONS TYPE "A" & "C"


DATE	REVISION	BY

ISSUE DATE: AUGUST 01, 2017


WORKING NUMBER GR-2

SHEET NUMBER 6204


STATE	PROJECT NO.
MISS.	



PLAN




SECTION A–A



SECTION B–B

* NOTE: IF FORESLOPE, SHOWN ELSEWHERE ON PLANS, IS OTHER THAN 6:1, TRANSITION WILL OCCUR IN AREA SHOWN.



DETAIL OF GUARDRAIL SECTION LAPS

GENERAL NOTES:

1. VALUES FOR "A", "B", "C" AND "D" WILL BE SHOWN ELSEWHERE ON THE PLANS.
2. FOR DETAILS PERTINENT TO INSTALLATION OF THE TERMINAL SECTION, SEE MANUFACTURER'S SPECIFICATIONS AND DRAWINGS OR ELSEWHERE ON PLANS
3. GUARDRAIL SECTIONS SHALL BE LAPPED IN THE DIRECTION OF TRAFFIC APPROACHING THE BRIDGE.
4. THE OVERALL LENGTH OF GUARDRAIL IS MEASURED FROM THE CONNECTING END ON THE BRIDGE.
5. IN THE ABSENCE OF A BRIDGE END PAVEMENT RAIL, CONNECT THE BRIDGE END SECTION TO THE BRIDGE RAIL (SEE WK. NOS. GR-2 THRU GR-2G). THE SHOULDER WIDTH AT THE BRIDGE END PAVEMENT RAIL OR BRIDGE END RAIL SHOULD BE SUFFICIENTLY WIDE TO PROVIDE A MINIMUM OF 2'-0" BEHIND THE BACK OF POST BEFORE THE SLOPE BREAK (HINGEPOINT).
6. TYPE, DETAILS AND LIMITS OF GUARDRAIL BRIDGE END SECTION WILL BE SHOWN ELSEWHERE ON THE PLANS.
7. W = SHOULDER WIDTH + FORESLOPE WIDTH. DIMENSIONS FOUND ELSEWHERE ON THE PLANS.

DATE	REVISION	BY

MISSISSIPPI DEPARTMENT OF TRANSPORTATION
ROADWAY DESIGN DIVISION
STANDARD PLAN

GUARDRAIL: TYPICAL INSTALLATION AT BRIDGE APPROACHES FOR 2–LANE, 2–WAY HIGHWAY


MDOT MISSISSIPPI DEPARTMENT OF TRANSPORTATION

WORKING NUMBER GR-4A


ISSUE DATE: AUGUST 01, 2017

SHEET NUMBER 6215

STATE	PROJECT NO.
MISS.	




ANCHOR PLATE ASSEMBLY DETAILS




TERMINAL POST FOR FOUNDATION TUBE INSTALLATION

NOTE: TERMINAL POST SHALL BE MADE OF S4S TIMBER WITH a STRESS GRADE OF 1200 lbs/in .



STEEL TUBE ANCHOR


NOTE: TERMINAL POST SHALL BE ABLE TO SLIDE INTO THE TOP OF THIS SECTION SO THE ACTUAL INSIDE DIMENSIONS OF THIS GALVANIZED TUBE CANNOT BE LESS THAN 7½" X 5½".




"W" BEAM TERMINAL CONNECTOR PLATE

NOTES:


1. THE "W" BEAM TERMINAL CONNECTOR SHALL BE AASHTO M 180 CORRUGATED SHEET STEEL, CLASS B, TYPE 1.
2. SPLICE-BOLT SLOTS MAY ALSO BE ORIENTED AT 50° (ON THE FLAT) INSTEAD OF Ø° AS SHOWN.



ANCHOR PLATE




BRACKET




SOIL PLATE


NOTE: 2 REQUIRED




BEARING PLATE




SHELF ANGLE BRACKET



END PLATE




CABLE ANCHOR ASSEMBLY




PLAIN ROUND WASHER


PLAIN ROUND WASHERS			
WASHER	A (NOM.)	B (NOM.)	C (NOM.)
"F"	11/16"	1¾"	9/64"
"H"	1 1/16"	2"	9/64"



GUARDRAIL BOLT



RECESSED NUT




RECTANGULAR GUARDRAIL PLATE WASHER


GUARDRAIL BOLTS		
BOLT	L	T (MIN.)
"A"	1¼"	1"
"B"	12"	4"
"C"	14"	4"
"D"	22"	4"
"E"	24"	4"
"F"	33"	4"
	2"	1¾"
	10"	4"
	25"	4"

NOTES:


1. ALL GUARDRAIL BOLTS ARE ⅝" - 11 UNC THREAD PITCH.
2. IF ANY BOLT EXTENDS MORE THAN ¼" FROM THE NUT, THE BOLT SHOULD BE TRIMMED BACK.



HEX NUT AND BOLT "F"



HEX NUT "H"




BREAKAWAY TERMINAL POST SLEEVE

FASTENER DETAILS


DATE	REVISION	BY	MISSISSIPPI DEPARTMENT OF TRANSPORTATION ROADWAY DESIGN DIVISION STANDARD PLAN	
			GUARDRAIL: MISCELLANEOUS HARDWARE	
ISSUE DATE: AUGUST Ø1, 2017				WORKING NUMBER GR-HW SHEET NUMBER 6221

STATE	PROJECT NO.
MISS.	


ROADSIDE SIGN IN RURAL AREA



ROADSIDE SIGN IN RURAL AREA




ROADSIDE SIGN IN BUSINESS, COMMERCIAL, OR RESIDENTIAL AREA




⚠1 * THE 2 FT. MINIMUM OFFSET APPLIES ONLY TO STANDARD SIGNS MOUNTED ON U-POSTS OR SQUARE TUBE POSTS. ALL STANDARD SIGNS MOUNTED ON PIPE WILL BE OFFSET A MINIMUM OF 4 FT FROM FACE OF CURB. RAMP DESTINATION SIGNS WILL BE OFFSET 4 FT. FROM THE SHOULDER BREAK.


WARNING SIGN WITH ADVISORY SPEED PLAQUE IN RURAL AREA



ROADSIDE ASSEMBLY IN RURAL AREA



INTERSTATE OR FREEWAY SIGN WITH SECONDARY SIGN




* 7 FT IF NO NECESSARY SECONDARY SIGN ⚠1


OVERHEAD SIGN




SIGN ON NOSE OF MEDIAN



SIGNS IN ISLANDS OR BEHIND CURB USING U–POSTS OR PIPE POSTS



ELEVATION



PLAN

⚠1 * THE 2 FT. MINIMUM OFFSET APPLIES ONLY TO STANDARD SIGNS MOUNTED ON U-POSTS. ALL STANDARD SIGNS MOUNTED ON PIPE WILL BE OFFSET A MINIMUM OF 4 FT. RAMP DESTINATION SIGNS WILL BE OFFSET 4 FT. FROM THE SHOULDER BREAK.

GENERAL NOTES:

⚠1 1. SEE SECTION 2A-16 OF THE MUTCD FOR REDUCED LATERAL OFFSET DISTANCES THAT MAY BE USED IN AREAS WHERE LATERAL OFFSETS ARE LIMITED, AND IN BUSINESS, COMMERCIAL, OR RESIDENTIAL AREAS WHERE SIDEWALK WIDTH IS LIMITED OR WHERE EXISTING POLES ARE CLOSE TO THE CURB.

2. SIGNS SHALL BE LOCATED OUTSIDE THE CLEAR ZONE UNLESS PLACED ON A BREAKAWAY OR YIELDING SUPPORT.

		STN	BY
	REVISED TEXT		
	REVISION		
12/11/25	DATE		

MISSISSIPPI DEPARTMENT OF TRANSPORTATION
ROADWAY DESIGN DIVISION
STANDARD PLAN

STANDARD ROADSIDE SIGN ASSEMBLY AND INSTALLATION


MDOT MISSISSIPPI DEPARTMENT OF TRANSPORTATION

WORKING NUMBER SN-4


ISSUE DATE: AUGUST 01, 2017

SHEET NUMBER 6306


STATE	PROJECT NO.
MISS.	





TYPICAL ROUTE ASSEMBLY




TYPICAL STACKED ROUTE ASSEMBLY









FOOTING DETAIL FOR
U–SECTION POSTS

GENERAL NOTES:

1. UNLESS OTHERWISE SPECIFIED, HORIZONTAL BRACES ARE 7/16" X 2 1/2" X VARIABLE LENGTH FLAT STEEL BARS. BARS ARE WELDED TO PIPE AS SHOWN. WHEN FABRICATION IS COMPLETE, POST SHALL BE GALVANIZED AS PER SECTION 630 OF THE STANDARD SPECIFICATION.
2. HOLES IN FLAT BARS ARE 3/8" DIAMETER.
3. SIGNS ARE FASTENED TO FLAT BARS AND U-SECTION POST WITH 5/16" BOLTS, WITH FLAT WASHER AND LOCK-NUTS.
4. GROUND PLATE NOT REQUIRED ON U-SECTION POST.
5. SEE WK. NO. SN-4B FOR DETAIL OF 3" PIPE FOOTING DETAIL.

BY	REVISION	DATE

MISSISSIPPI DEPARTMENT OF TRANSPORTATION
ROADWAY DESIGN DIVISION
STANDARD PLAN


STANDARD ROADSIDE SIGN ASSEMBLY AND INSTALLATION

ISSUE DATE: AUGUST 01, 2017

WORKING NUMBER
SN-4A


SHEET NUMBER
6307

STATE	PROJECT NO.
MISS.	




DISTANCE REFERENCE SIGN MOUNTING ON OUTSIDE SHOULDER ALONG MAIN FACILITY

NOTE: SIGN MOUNTING ON LEFT LANE SHOULDER SHALL BE 90° OPPOSITE THE RIGHT LANE STATION. IF CONDITIONS ARE SUCH THAT MILE SIGN CANNOT BE LOCATED WITHIN 50 FEET OF ITS TRUE LOCATION, IT SHALL BE OMITTED ENTIRELY.




DELINEATOR MOUNTING ON OUTSIDE SHOULDER ALONG MAIN FACILITY OR RAMP




DETAIL OF TYPE 3 OBJECT MARKER

NOTE: COLORS- BLACK AND YELLOW. STRIPING SHOWN ABOVE FOR RIGHT SIDE ONLY. STRIPES SLANT DOWNWARD TO THE RIGHT FOR LEFT SIDE OF BRIDGE END. SEE DETAIL BELOW.




REAR VIEW OF TYPE 3 OBJECT MARKER OR DISTANCE REFERENCE SIGN ASSEMBLY


NOTE: TYPE 3 OBJECT MARKER AND DISTANCE REFERENCE SIGNS SHALL BE FASTENED TO U-SECTION POSTS WITH 5/16" DIA. BLIND FASTENERS OF THE COLLAR TYPE.




DETAIL OF SINGLE WHITE OR SINGLE YELLOW DELINEATOR



DETAIL OF DOUBLE WHITE OR DOUBLE YELLOW DELINEATOR




REAR VIEW OF DELINEATOR ASSEMBLY




MOUNTING DETAIL


NOTE: DELINEATORS SHALL BE FASTENED TO U-SECTION POSTS WITH 1/4" DIA. BLIND FASTENERS OF THE COLLAR TYPE.



DELINEATOR MOUNTING ON OUTSIDE SHOULDER WITH MOUNTABLE CURB ALONG MAIN FACILITY OR RAMP



DELINEATOR MOUNTING ON INTERCHANGE LOOPS WITH UNMOUNTABLE CURB ON INSIDE



DETAIL OF TYPE 3 OBJECT MARKER INSTALLATION

GENERAL NOTES:

1. DELINEATORS AND TYPE 3 OBJECT MARKER SHALL BE RETROREFLECTIVE SHEETING ON 0.080" THICK ALUMINUM SHEET OR 14 GAGE GALVANIZED SHEET STEEL.
2. DELINEATOR, TYPE 3 OBJECT MARKER AND DISTANCE REFERENCE SIGN POSTS SHALL BE GALVANIZED STEEL. THE POSTS SHALL BE FABRICATED BEFORE THE METAL IS GALVANIZED.
3. WEIGHT WITHOUT GROUND PLATES:
   A. DELINEATOR POST 7'-0" - 2.0 lb/ft TO 2.5 lb/ft
   B. TYPE 3 OBJECT MARKER POST 9'-0" - 2.5 lb/ft TO 3.0 lb/ft
   C. DISTANCE REFERENCE SIGN POST 10'-0", 11'-0", & 12'-0" - 3.0 lb/ft TO 3.5 lb/ft
4. UNIT PRICE OF DELINEATORS AND TYPE 3 OBJECT MARKERS SHALL INCLUDE COST OF POST. DISTANCE REFERENCE SIGN POST WILL BE PAID FOR PER FOOT.
5. RADIUS IN BENDS OF POST CROSS SECTION NOT TO EXCEED 13/16" FOR HOT ROLLED SECTION.
6. GROUND PLATE NOT REQUIRED ON U-SECTION POST.

STN	BY	REVISED TEXT REVISION	12/11/25 DATE

MISSISSIPPI DEPARTMENT OF TRANSPORTATION
ROADWAY DESIGN DIVISION
STANDARD PLAN


TYPICAL INSTALLATION AND DETAILS OF DELINEATORS AND DISTANCE REFERENCE SIGNS

ISSUE DATE: AUGUST 01, 2017


WORKING NUMBER SN-8

SHEET NUMBER 6314


STATE	PROJECT NO.
MISS.	




BRIDGE APPROACH INSTALLATION
(ONE-WAY TRAFFIC)




BRIDGE APPROACH INSTALLATION
(TWO-WAY TRAFFIC)




GRAPHIC SHOWING SPACINGS OF GUARDRAIL DELINEATORS
AT SOME COMMONLY USED BRIDGE APPROACHES



ROADSIDE OBSTACLE INSTALLATION–LENGTH 250' OR LESS
(ONE-WAY TRAFFIC)




ROADSIDE OBSTACLE INSTALLATION–LENGTH 250' OR LESS
(TWO-WAY TRAFFIC)




EMBANKMENT OR ROADSIDE OBSTACLE INSTALLATION–LENGTH GREATER THAN 250'
(ONE-WAY TRAFFIC)

NOTE: ONE-WAY TRAFFIC SHOWN. DELINEATOR SPACING FOR TWO-WAY TRAFFIC SIMILAR. DELINEATOR COLOR WILL BE THE SAME AS THE ADJACENT PAVEMENT EDGE MARKING. THE FIRST THREE (3) MARKERS WILL FACE TRAFFIC IN OFF LANE FOR TWO-WAY TRAFFIC AS SHOWN IN DRAWING FOR OBSTACLE INSTALLATION FOR TWO-WAY TRAFFIC.



PLAN VIEWS

TYPICAL FLEXIBLE POST DELINEATOR
GUARDRAIL INSTALLATION



DETAIL OF FLEXIBLE
GUARDRAIL DELINEATOR

GENERAL NOTES:

1. THE UNIT PRICE OF DELINEATOR INCLUDES: COST(S) OF DELINEATOR FACE(S), POST, HARDWARE AND INSTALLATION.

⚠1 2. DELINEATORS SHALL CONSIST OF RETROREFLECTIVE DEVICES THAT ARE CAPABLE OF CLEARLY RETROREFLECTING LIGHT UNDER NORMAL ATMOSPHERIC CONDITIONS FROM A DISTANCE OF 1000 FEET WHEN ILLUMINATED BY THE HIGH BEAMS OF STANDARD AUTOMOBILE LIGHTS.

⚠1 3. FOR THE SPACING OF DELINEATORS IN HORIZONTAL CURVES ON ROADWAYS OR BRIDGES, SEE TABLE 3G-1, MUTCD 11th EDITION, FOR SPACING REQUIREMENTS.

⚠1 4. DELINEATORS FOR GUARDRAIL SHALL BE MOUNTED ON FLEXIBLE POSTS AS FOLLOWS:

THE DELINEATOR POSTS WILL BE FROM MDOT'S "APPROVED PRODUCTS LIST" AND WILL BE FASTENED TO GUARDRAIL POST IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATION.

12/11/25	DATE	STN	BY
	REVISION	REVISED TEXT	

MISSISSIPPI DEPARTMENT OF TRANSPORTATION
ROADWAY DESIGN DIVISION
STANDARD PLAN

TYPICAL GUARDRAIL DELINEATION

MDOT MISSISSIPPI DEPARTMENT OF TRANSPORTATION


WORKING NUMBER
SN-8C

SHEET NUMBER
6317

ISSUE DATE: AUGUST 01, 2017

STATE	PROJECT NO.
MISS.	

DRAWING NOT INTENDED TO REPRESENT PAVEMENT MARKING DETAILS



NOTE: WHEN MULTIPLE BRIDGES ARE ALONG A ROUTE AND ARE 1000 FEET OR LESS FROM EACH OTHER, W8-13 (BRIDGE ICES BEFORE ROAD) SIGNS ARE NOT TO BE PLACED BETWEEN THE BRIDGES.


UNDIVIDED HIGHWAY DETAIL

SIGN QUANTITES FOR UNDIVIDED HIGHWAY (PER SIGN)					
MUTCD NUMBER	STANDARD ROAD SIGNS SHEET ALUMINUM 0.080" THICKNESS	STANDARD ROAD SIGNS SHEET ALUMINUM 0.125" THICKNESS	SQUARE FEET 0.080" THICKNESS	SQUARE FEET 0.125" THICKNESS	U-SECTION POST (3-P)
OM3-L	12" X 36"		3 SF		9 LF
OM3-R	12" X 36"		3 SF		9 LF
W8-13		36" X 36"		9 SF	15 LF

SIGN QUANTITES FOR DIVIDED HIGHWAY (PER SIGN)								
MUTCD NUMBER	STANDARD ROAD SIGNS SHEET ALUMINUM 0.080" THICKNESS	STANDARD ROAD SIGNS SHEET ALUMINUM 0.125" THICKNESS	SQUARE FEET 0.080" THICKNESS	SQUARE FEET 0.125" THICKNESS	U-SECTION POST (3-P)	STANDARD 4" PIPE	STRUCTURAL BARS 7/8" X 2½"	FOOTING CLASS "B" CONCRETE
OM3-L	12" X 36"		3 SF		9 LF			
OM3-R	12" X 36"		3 SF		9 LF			
W8-13		48" X 48"		16 SF		16.5 LF	19.35 LB (2@2'-7")	0.13 CY

⚠ ① RETROREFLECTIVE ADHESIVE SHEETING WITH ALTERNATING BLACK AND YELLOW STRIPES (SLOPING DOWNWARD) (OM101-1L, OM101-1R) AT AN ANGLE OF 45 DEGREES (IN THE DIRECTION TRAFFIC IS TO PASS) IS REQUIRED ON THE END OF THE TERMINAL END SECTION. NOT A SEPARATE PAY ITEM. COST TO BE ABSORBED IN GUARD RAIL.

* TABLE 2C-3 MUTCD	
SPEED (MPH)	MINIMUM PLACEMENT (FEET)
35	250 ⚠1
40	305 ⚠1
45	360 ⚠1
50	425 ⚠1
55	495 ⚠1
60	570 ⚠1
65	645 ⚠1
70	730 ⚠1



DIVIDED HIGHWAY DETAIL

STN	BY	REVISED TEXT	REVISION
12/11/25		DATE	

MISSISSIPPI DEPARTMENT OF TRANSPORTATION
ROADWAY DESIGN DIVISION
STANDARD PLAN


SIGNING DETAILS FOR BRIDGE APPROACHES

WORKING NUMBER SN-9

ISSUE DATE: AUGUST 01, 2017


SHEET NUMBER 6318

STATE	PROJECT NO.
MISS.	



STANDARD BARRICADES

1. THE RETROREFLECTIVE MARKING FOR BARRICADE RAILS SHALL BE ORANGE AND WHITE (SLOPING DOWNWARD AT AN ANGLE OF 45° IN THE DIRECTION THAT TRAFFIC IS TO PASS).
2. RAIL STRIPE SHOULD BE 6 INCHES, EXCEPT THAT 4-INCH WIDE STRIPES MAY BE USED IF RAIL LENGTHS ARE LESS THAN 36 INCHES.
3. DO NOT PLACE SANDBAGS OR OTHER DEVICES ON BARRICADE RAILS TO PROVIDE MASS SANDBAGS, HOWEVER, MAY BE PLACES AS BALLAST TO THE LOWER PARTS OF THE FRAME OR THE STAYS TO BARRICADES.
4. FOR ADDITIONAL INFORMATION OR DETAILS, SEE MUTCD, LATEST EDITION.
5. BARRICADES ARE CLASSIFIED BY FHWA AS CATEGORY II WORK ZONE DEVICES. A LIST OF CRASHWORTHY BARRICADES AND OTHER CATEGORY II DEVICES CAN BE FOUND ON FHWA'S WEBSITE: http://highways.dot.gov/safety/RwD/reduce-crash-severity
6. WHERE ROAD USERS INCLUDE PEDESTRIANS, THE PROVISION OF SUPPLEMENTAL AUDIBLE INFORMATION OR DETECTABLE BARRIERS OR BARRICADES SHOULD BE PROVIDED FOR PEOPLE WITH VISION DISABILITIES.
7. BARRICADE RAIL SUPPORTS SHOULD NOT PROJECT INTO PEDESTRIAN CIRCULATION ROUTES MORE THAN 4 INCHES FOR THE SUPPORTS LOCATED BETWEEN 27 INCHES TO 80 INCHES ABOVE THE EXISTING SURFACE.



BARRICADE CLOSING A ROAD


BARRICADE CHARACTERISTICS

	I	II	III
WIDTH OF RAIL **	8" MIN. - 12" MAX.	8" MIN. - 12" MAX.	8" MIN. - 12" MAX.
LENGTH OF RAIL **	24" MIN. / 96" MAX.	24" MIN. /96" MAX.	48" MIN. / 96" MAX.
WIDTH OF STRIPE *	6"	6"	6"
HEIGHT	36" MIN.	36" MIN.	60" MIN.
NUMBER OF RETROREFLECTORIZED RAIL FACES	2 (ONE EACH DIRECTION)	4 (TWO EACH DIRECTION)	3 IF FACING TRAFFIC IN ONE DIRECTION 6 IF FACING TRAFFIC IN TWO DIRECTIONS

1


* 1. FOR RAILS LESS THAN 36" LONG, 4" WIDE STRIPES MAY BE USED.

** 2. BARRICADES INTENDED FOR USE ON EXPRESSWAYS, FREEWAYS AND OTHER HIGH SPEED ROADWAYS, SHALL HAVE A MINIMUM OF 270 in^2 OF REFLECTIVE AREA FACING TRAFFIC.




WING BARRICADES

1. WING BARRICADES ARE TYPE III BARRICADES ERECTED ON THE SHOULDER ON ONE OR BOTH SIDES OF THE PAVEMENT TO GIVE THE SENSATION OF A NARROWING OR RESTRICTED ROADWAY. WING BARRICADES MAY BE USED AS A MOUNTING FOR THE ADVANCE WARNING SIGNS OR FLASHERS.
2. WING BARRICADES SHOULD BE USED:
   A. IN ADVANCE OF A CONSTRUCTION PROJECT EVEN WHEN NO PART OF THE ROADWAY IS ACTUALLY CLOSED.
   B. IN ADVANCE OF ALL BRIDGE OR CULVERT WIDENING OPERATIONS.




1 RETROREFLECTIVE CHEVRON ALIGNMENT SIGN DETAIL (W1–8)

1. A CHEVRON SIGN CONSISTS OF A BLACK CHEVRON TYPE MARKING ON AN ORANGE BACKGROUND AND SHALL POINT IN THE DIRECTION OF TRAFFIC FLOW.
2. THE CHEVRON SIGN SHALL BE MOUNTED ON CRASHWORTHY SUPPORT.
3. CHEVRON SIGNS MAY BE USED TO SUPPLEMENT OTHER STANDARD DEVICES WHERE ONE OR MORE LANES ARE CLOSED FOR CONSTRUCTION OR MAINTENANCE. THEY SHOULD BE PLACED APPROXIMATELY 2'-0" BEHIND THE LANE TRANSITION STRIPE.
4. CHEVRON SIGNS SHALL BE INSTALLED AT A MINIMUM HEIGHT OF 4 FEET MEASURED VERTICALLY FROM THE BOTTOM OF THE SIGN TO THE ELEVATION OF THE NEAR EDGE OF THE TRAVELWAY.




TYPE 3 OBJECT MARKER (OM3–R)


1. TYPE 3 OBJECT MARKERS SHALL BE USED AT ALL EXPOSED BRIDGE ABUTMENTS AND AT OTHER LOCATIONS AS DEEMED NECESSARY BY THE ENGINEER.
2. THE OM3-R IS SHOWN. THE OM3-L IS SIMILAR EXCEPT THE STRIPES SLOPE DOWNWARD FROM THE UPPER LEFT SIDE TO THE LOWER RIGHT SIDE AND SHALL BE PLACED ON THE LEFT SIDE OF THE OBJECT.
3. THE INSIDE EDGE OF THE MARKER SHALL BE IN LINE WITH THE INNER EDGE OF THE OBSTRUCTION.
4. THE STRIPING SHALL CONSIST OF ALTERNATING BLACK AND RETOREFLECTIVE YELLOW SLOPING DOWNWARD TOWARD THE SIDE ON WHICH TRAFFIC IS THE PASS.




1 PLASTIC DRUM DETAIL



1 TUBULAR MARKER DETAIL



1 PLASTIC CONE DETAIL (28" – 36")



1 PLASTIC CONE DETAIL (36" OR GREATER)

1. PLASTIC DRUMS, TUBULAR MARKERS, OR PLASTIC CONES SHALL BE ON END AND USED AS AN EXPEDIENT METHOD FOR TRAFFIC CHANNELIZATION. THE COLOR AND MARKING OF THE DEVICE USED SHALL BE CONSISTENT WITH MARKING STANDARDS FOR BARRICADE. THE PREDOMINANT COLOR ON THE DEVICE USED SHALL BE ORANGE WITH RETROREFLECTIVE, HORIZONTAL, CIRCUMFERENTIAL WHITE STRIPES AS SHOWN ON THE DETAILS.
2. DRUMS, TUBULAR MARKERS, OR PLASTIC CONES SHOULD NEVER BE PLACED IN THE ROADWAY WITHOUT WARNING SIGNS.
3. WHERE PRACTICAL PLASTIC DRUMS, TUBULAR MARKERS, OR PLASTIC CONES SHOULD BE PLACED NO CLOSER THAN 3'-0" FROM THE EDGE OF TRAVELED LANE.
4. BALLAST SHALL NOT BE PLACED ON THE TOP OF THE DRUM.

DATE	REVISION	BY
12/11/25	REVISED TEXT AND DETAILS.	STN

MISSISSIPPI DEPARTMENT OF TRANSPORTATION
ROADWAY DESIGN DIVISION
STANDARD PLAN

HIGHWAY SIGN AND BARRICADE DETAILS FOR CONSTRUCTION PROJECTS

MDOT MISSISSIPPI DEPARTMENT OF TRANSPORTATION

WORKING NUMBER TCP-8

SHEET NUMBER 6358

ISSUE DATE: AUGUST 01, 2017

DESCRIPTION OF SHEETS SPECIAL DESIGN SHEETS - BRIDGE DRAWINGS	WORKING NUMBER	SHEET NUMBER
DETAILED INDEX	DI-BR-1	8001
BRIDGE AT STA. 10+01.02		
McCLUER ROAD ACROSS CANEY CREEK RELIEF	1 OF 4	8002
McCLUER ROAD ACROSS CANEY CREEK RELIEF	2 OF 4	8003
BORING LOG	3 OF 4	8004
PRECAST PANEL DETAILS	4 OF 4	8005
PRECAST STANDARD DETAILS		
19' & 31' PRECAST CONCRETE SPANS FOR USE WITH BARRIER RAIL 28' & 30'		PC-02-09
19' x 3.5' PRECAST CONCRETE SLAB UNIT FOR USE WITH BARRIER RAIL		PC-05-09
PRECAST CONCRETE CAPS FOR USE WITH 19 FT. & 31 FT. PRECAST CONCRETE SPANS & BARRIER RAIL 28'-0" ROADWAY		PC-12-09
BEARING PAD & PLACEMENT DETAILS FOR USE WITH 23', 24', 26.5', 28', & 30' CLEAR ROADWAYS NORMAL AND 30° SKEW SPANS		PC-15-09
PRECAST ABUTMENT WINGWALL FOR USE WITH 19 FT. & 31 FT. PRECAST CONCRETE SPANS & BARRIER RAIL 28 FT. & 30 FT. ROADWAYS		PC-17-09
19'-0" SOLID TYPE BARRIER RAIL		PC-18-09

CHARLES TACHARIAN TAKAMAN
REGISTERED PROFESSIONAL ENGINEER
STATE OF MISSISSIPPI
06/26/2026

CITY OF JACKSON

DESIGNED BY: CZP
DETAILED BY: CZP
CHECKED BY: RCF
DATE: 03/13/2026

FMS CON: 109860/701000
PROJECT NO.: STP-7287-00(001)LPA
COUNTY: HINDS


DETAILED INDEX

DIR OF STRUCTURES, STATE BRIDGE ENGINEER - SCOTT WESTERFIELD, P.E.
DEP. DIR OF STRUCTURES, ASST. STATE BRIDGE ENGINEER - MICAH DEW, P.E.

WK. NO.
DI-BR-1

SHEET NO.
8001


9/15/2026 9:18:33 AM Detailed Index.dgn PLAN SHEET



ELEVATION WITH PROFILE ALONG ℄ APPROACH ROADWAY


Scale: $^{3}/_{16}$"= 1'-0"

NOTE: Geotextile Fabric Is Required Under All Riprap. All Riprap And Geotextile Fabric Shown On The Bridge Plans Are Included In The Bridge Quantities.



NOTE: Concrete For Pile Encasement Shall Be Class "AA" And Will Be Paid For As Bridge Concrete. Class "AA" Concrete With #67 Aggregate May Be Used For Pile Encasement. Pile Encasement Shall Be Reinforced With 6x6-W1.4xW1.4 Welded Wire Fabric Weighing 0.21 Lbs. Per Sq. Ft. (Not A Separate Pay Item) Or Synthetic Structural Fiber Applied At A Dosage Rate Of 4 Lbs. Per Cubic Yd. Synthetic Structural Fiber Shall Meet Requirements Of Special Provision No. 907-711 (Not A Separate Pay Item). Chamfer Corners Of Encasement ¾".

PILE ENCASEMENT DETAIL



PILE SPLICE DETAIL

NOTE: In Lieu Of Splice Plates, Prefabricated Splicers May Be Used. Prefabricated Splicers Shall Be Submitted For Approval By The Director Of Structures, State Bridge Engineer.

GENERAL NOTES:

Specifications: Mississippi Standard Specifications For Road And Bridge Construction, 2017.
No Change Of Plans Will Be Permitted Except By Written Approval Of The Director Of Structures, State Bridge Engineer. Minor Changes In Detail Of Design Or Construction Procedure May Be Authorized By The Director Of Structures, State Bridge Engineer Provided Such Changes Will Not Be Cause For Contract Price Adjustment.
Bridge Concrete Shall Be Class "AA".
No Payment Will Be Allowed For Excavation Incidental To The Construction Of End Bents.
Bar Bending Details Shall Be In Accordance With "Manual Of Standard Practice For Detailing Reinforced Concrete Structures" (ACI 315R-94).
Reinforcement Order Lists And Required Placing Plans Shall Be Furnished In Accordance With Section 805 Of The Mississippi Standard Specifications. Partial Submittals Are Not Acceptable.
Reinforcing Steel Shall Be ASTM A615, Grade 60, Unless Otherwise Noted.
Work For Which No Pay Item Is Provided In The Proposal Will Not Be Paid For Directly And Compensation Therefor Will Be Included In The Prices And Payments For Bid Items.

PILE NOTES:

PDA Test Piles Shall Be Driven As Permanent Piles At The Location Shown In The PDA Test Pile Schedule And Will Be Paid For As PDA Test Piles Only.
The Director Of Structures, State Bridge Engineer May Authorize PDA Test Piles Driven Outside The Structure Limits.
PDA Test Piles Shall Be Driven As A Continuous Operation, To The Bearing Capacity And The Minimum Ground Penetration Shown In The PDA TEST PILE SCHEDULE, Unless Otherwise Directed By The Director Of Structures, State Bridge Engineer.
Permanent Piles Shall Be Driven To An Elevation No Higher Than The Elevation Shown In The REQUIRED ULTIMATE PILE BEARING CAPACITY AND TIP ELEVATION SCHEDULE.
The Tip Elevation Of Piling, For Hydraulic Structures, May Be Determined By The Scour Line.
When Feasible, Bearing Piles Shall Be Driven Full Length And Be Spliced, Only, As Approved By The Director Of Structures, State Bridge Engineer.
Prefabricated Splices For H Piles Are Not Acceptable For Test Piles.
Welding Shall Be Done By The Electric Arc Process. Welders Shall Be Certified And Electrodes Shall Be Approved.
When Loading Tests Are Required, The Maximum Test Load Shall Be One And One Half (1½) Times The Minimum Pile Bearing Capacity.
Steel For HP Steel Piles shall Be A.S.T.M. A572, Grade 50.
PDA Test Piles Shall Require A 1 Day Restrike Unless Otherwise Directed By The Director Of Structures, State Bridge Engineer.
Pile Lengths And Driving Criteria Shall Be Provided Based On The Results Of The PDA Test Piles.
The Required Ultimate Pile Bearing Shown In The REQUIRED ULTIMATE PILE BEARING AND TIP ELEVATION SCHEDULE Includes The LRFD Resistance Factor For PDA Of 0.65.
Pile Hammer Leads Used For All PDA Test Piles And PDA Restrikes Shall Be Large Enough To Provide A Minimum Of 3" Of Clearance On Each Side Of The Pile In Order To Properly Place And Protect PDA Gages.
Steel HP Piles Shall Be Driven With A Maximum Rated Energy No Less Than 43,000 Ft-Lbs, But No Greater Than 70,100 Ft-Lbs To The Tip Elevations Specified Unless The Contractor's Drivability Analysis Utilizing The Contractor's Selected Alternative Hammer Is Approved By The Director's Of Structures, State Bridge Engineer.
Paint Exposed HP Piles Per Section 816 Of The Specifications With One Prime Coat Which Shall Be Grey In Color To 1 Foot Below The Groundline Elevation.

PDA TEST PILE SCHEDULE

Location	Minimum Length (Ft.)	Tip Elevation
1	45	231.0

REQUIRED ULTIMATE PILE BEARING CAPACITY AND TIP ELEVATION SCHEDULE

Location	Required Bearing (Tons)	Steel Piling	Estimated Length (Ft.)	Tip Elevation
1	51	HP14x89	50	
2	80	HP14x89	55	247.80
3	51	HP14x89	50	

500 YEAR SCOUR

Location	Elevation
1	265.55
2	267.80
3	265.55

ESTIMATED QUANTITIES

Item / Location	Conventional Static Pile Load Test (Each)	HP14x89 Steel Piling (L.F.)	PDA Test Pile HP Steel Pile (Each)	Pile Restrike (Each)	Bridge Concrete Class "AA" (C.Y.)	19' Precast Concrete Slab Units, 3'-6" Interior (Each)	19' Precast Concrete Slab Units, 3'-6" Exterior (Each)	19' Precast Barrier Rail Units (Each)	31' Precast Concrete Caps, Intermediate Unit (Each)	31' Precast Concrete Caps, End Unit With Wall (Each)	Loose Riprap Size 300 (Ton)	Geotextile Under Riprap (S.Y.)	Precast Panels (S.Y.)
Spans						12	4	4					
End Bents	1	550.0	1	1						2	80.8	48.0	71.1
Int. Bents		220.0			2.23				1				
Totals	1	770.0	1	1	2.23	12	4	4	1	2	80.8	48.0	71.1

SEISMIC DESIGN DATA:

Seismic Performance Zone. . . . . Zone 1
Site Class Definition. . . . . Site Class D
Importance Category. . . . . Other

DRAINAGE DATA:

Drainage Area. . . . . 7.76 Sq. Mi.
Q100 (U.S.G.S.). . . . . 11,008 c.f.s
Effective Area. . . . . 224 Sq. Ft.

DESIGN DATA:

Specifications. . . . . A.A.S.H.T.O. 2007, Through 2009 Interims
Loading. HL-93
Roadway Width. . . . . 28'-0" Gutter To Gutter

CHARLES TACHARIAN TAKAMAN
REGISTERED PROFESSIONAL ENGINEER
STATE OF MISSISSIPPI
06/26/2026

CITY OF JACKSON

DESIGNED BY: CZP
DETAILED BY: CZP
CHECKED BY: RCF
DATE: 03/13/2026

FMS CON: 109860/701000
PROJECT NO.: STP-7287-00(001)LPA
COUNTY: HINDS


McCLUER ROAD ACROSS CANEY CREEK RELIEF

DIR OF STRUCTURES, STATE BRIDGE ENGINEER - SCOTT WESTERFIELD, P.E.
DEP. DIR OF STRUCTURES, ASST. STATE BRIDGE ENGINEER - MICAH DEW, P.E.

WK. NO. **2 OF 4**

SHEET NO. **8002**

PLAN SHEET
9/15/2026 9:18:37 AM Layout.dgn



FOUNDATION PLAN

Scale: $\frac{3}{16}$"= 1'-0"

***NOTE: *Abandoned Water Lines Shall Be Removed From Sta. 9+90.00 To Sta. 10+50.00. Cost To Be Included In Pay Item No. 202-B023-Removal Of Bridge.*

NOTE: *Geotextile Fabric Is Required Under All Riprap. All Riprap And Geotextile Fabric Shown On The Bridge Plans Are Included In The Bridge Quantities.*

CHARLES TACHARIAN TAKCHMAN
REGISTERED PROFESSIONAL ENGINEER
STATE OF MISSISSIPPI
06/26/2026

CITY OF JACKSON

DESIGNED BY: CZP
DETAILED BY: CZP
CHECKED BY: RCF
DATE: 03/13/2026

FMS CON: 109860/701000
PROJECT NO.: STP-7287-00(001)LPA
COUNTY: HINDS

McCLUER ROAD ACROSS CANEY CREEK RELIEF

DIR OF STRUCTURES, STATE BRIDGE ENGINEER - SCOTT WESTERFIELD, P.E.
DEP. DIR OF STRUCTURES, ASST. STATE BRIDGE ENGINEER - MICAH DEW, P.E.

WK. NO. **3 OF 4**

SHEET NO. **8003**

PLAN SHEET


9/15/2026 9:18:39 AM Layout.dgn

UNIFIED SOIL CLASSIFICATION SYSTEM

MAJOR DIVISIONS			SYMBOL & LETTER	DESCRIPTION
COARSE-GRAINED SOILS More than half of material larger than No. 200 sieve size	GRAVELS More than half of coarse fraction larger than No.4 sieve size	Clean Gravels (Little or no fines)	GW	WELL GRADED GRAVEL, GRAVEL-SAND MIXTURE
			GP	POORLY GRADED GRAVEL, GRAVEL-SAND MIXTURE
		Gravels with fines (Appreciable amount of fines)	GM	SILTY GRAVEL, GRAVEL-SAND-SILT MIXTURE
			GC	CLAYEY GRAVEL, GRAVEL-SAND-CLAY MIXTURE
	SANDS More than half of coarse fraction smaller than No.4 sieve size	Clean Sands (Little or no fines)	SW	WELL GRADED SAND, GRAVELLY SAND
			SP	POORLY GRADED SAND, GRAVELLY SAND
		Sands with fines (Appreciable amount of fines)	SM	SILTY SAND, SAND-SILT MIXTURE
			SC	CLAYEY SAND, SAND-CLAY MIXTURE
FINE-GRAINED SOILS More than half of material smaller than No. 200 sieve size	SILTS AND CLAYS	Liquid limit less than 50	ML	SILT WITH LITTLE OR NO PLASTICITY
			ML	CLAYEY SILT, SILT WITH SLIGHT TO MEDIUM PLASTICITY
			ML	SANDY SILT
			CL	SILTY CLAY, LOW TO MEDIUM PLASTICITY
			CL	SANDY CLAY, LOW TO MEDIUM PLASTICITY (30% TO 50% SAND)
	SILTS AND CLAYS	Liquid limit greater than 50	MH	SILT, HIGH PLASTICITY
			CH	CLAY, HIGH PLASTICITY
			OH	ORGANIC CLAY OF MEDIUM TO HIGH PLASTICITY
HIGHLY ORGANIC SOILS			PT	PEAT, HUMUS, SWAMP SOIL

TERMS CHARACTERIZING SOIL STRUCTURE

Slickensided	- Clays with polished and striated planes created as a result of volume changes related to shrinking, swelling and/orchanges in overburden pressure.
Fissured	- Clays with a blocky or jointed structure generally created by seasonal shrinking and swelling.
Laminated	- Composed of thin alternating layers of varying color and texture.
Calcareous	- Containing appreciable quantities of calcium carbonate.
Parting	- Paper thin (less than 1/8 Inch).
Seam	- 1/8 inch to 3 inch thickness.
Layer	- Greater than 3 inches in thickness.



FOR CLASSIFICATION OF FINE GRAINED SOILS

TERMS CHARACTERIZING SOIL STRUCTURE

COARSE-GRAINED SOILS		FINE-GRAINED SOILS	
DENSITY	PENETRATION RESISTANCE, N Blows per Foot	CONSISTANCY	COHESION Kips/Sq. Ft	PENETRATION RESISTANCE, N Blows per Foot
Very loose	0 - 4	Very Soft	<0.25	0 - 1
Loose	5 - 10	Soft	0.25 - 0.50	2 - 4
Medium Dense	11 - 30	Medium Stiff	0.50 - 1.00	5 - 8
Dense	31 - 50	Stiff	1.00 - 2.00	9 - 15
Very Dense	>4.00	Very Stiff	2.00 - 4.00	16 - 30
		Hard	>4.00	>30

PARTICLE SIZE IDENTIFICATION			RELATIVE COMPOSITION	
Cobbles	-	Greater than 3 inches	Slightly	5 - 15%
Gravel	-	Coarse-3/4 inch to 3 inches Fine-4.76 mm to 3/4 inch	With	16 - 29%
Sand	-	Coarse-2 mm to 4.76 mm Medium-0.42 mm to 2 mm Fine-0.074 mm to 0.42 mm	Sandy (or gravelly)	30 - 50%
Silt & Clay	-	Less than 0.074 mm		

SAMPLE TYPES
(Shown in Sample Column)



CLASSIFICATION, SYMBOLS AND TERMS USED ON GRAPHICAL BORING LOGS


BURNS COOLEY DENNIS, INC.

FIGURE 2

LOG OF BORING NO. 1
PROPOSED MCCLEUR ROAD BRIDGE REPLACEMENT
BRIDGE NO. SA25-157
HINDS COUNTY, MISSISSIPPI

TYPE: 6" Short-flight auger to 10', then rotary wash to completion,

LOCATION: See Figure 1



Note: SPT performed using a calibrated Auto-Hammer. An energy correction factor of 1.43 is applied to calculate the plotted N60 values.

BORING DEPTH: 100 ft	COMMENTS: Borehole filled with cement-bentonite grout after completion of drilling and sampling. GPS Coordinates N 32° 14' 25.0" W 90° 14' 12.9"	GROUNDWATER DATA: No free water encountered during auger drilling.
DATE: 05/05/25		

250165.GPJ

FIGURE 3

PLAN SHEET

9/15/2026 9:18:42 AM Boring Logs.dgn



06/26/2026

CITY OF JACKSON

DESIGNED BY: CZP
DETAILED BY: CZP
CHECKED BY: RCF
DATE: 03/13/2026


FMS CON: 109860/701000
PROJECT NO.: STP-7287-00(001)LPA
COUNTY: HINDS

BORING LOG

DIR OF STRUCTURES, STATE BRIDGE ENGINEER - SCOTT WESTERFIELD, P.E.
DEP. DIR OF STRUCTURES, ASST. STATE BRIDGE ENGINEER - MICAH DEW, P.E.


WK. NO. **3 OF 4**

SHEET NO. **8004**




TYPICAL PRECAST PANEL ELEVATION

NOTE: *Bars H Shall Be Flame Cut And Painted With Epoxy Mastic Primer In Field After Final Panel Placement.*




SECTION A-A




KEY DETAILS

NOTE: *½" Bituminus Material Shall Be Placed At Joint Locations Between Panels, Ensuring No Overhang On Front Face.*




SECTION B-B



INSTALLATION OF PRECAST PANEL

NOTE: *Panels Shall Be Centered Between Piles And Edges Of Stacked Panels Shall Line Up.*



BARS H - #5

BAR BENDING DETAILS


Dimensions Are Out To Out

PRECAST PANEL NOTES:

The Panels Shall Be Fabricated In Accordance With Section 804 Of The Standard Specifications And As Noted Below.
The Panels Shall Be Fully Supported Until The Concrete Reaches A Minimum Compressive Strength Of 1,000 P.S.I. And May Be Shipped After The Concrete Reaches A Minimum Compressive Strength Of 3,000 P.S.I.
The Back (Fill) Face Of The Panels Shall Be Screeded To Eliminate Open Pockets Of Aggregate And Surface Distortions In Excess Of ¼".
The Panels Shall Be Cast On Flat Surface Using Either Wood Or Metal Forms.
The Panels Shall Be Marked With The Date Of Manufacture And Piece Mark On The Rear Face.
All Panels Shall Be Handled, Stored And Shipped In Such A Manner As To Prevent Chipping, Discoloration, Cracks And Excessive Bending Stresses. Panels In Storage Shall Be Supported On Firm Blocking To Protect The Surface Finish.
The Panel Dimensions Shall Be Within ½" Of The Dimensions Shown.
Any Panel That Indicates Imperfect Molding, Honeycombing (open Textured Concrete), Cracking, Severe Chipping Or Extreme Color Variation Shall Be Rejected.
Exposed Face Shall Receive A Class 2 Rubbed Or Spray Finish In Accordance With The Specifications.

STRUCTURAL STEEL NOTES:

All Structural Steel In The Precast Panels Shall Be A.S.T.M. A709, Grade 50.



TYPICAL WALL UNDERDRAIN

NOTE: *The 6" Perforated Pipe Shall Be Continuous Along The Entire Length Of The Wall. The Minimum Slope Shall Be 1%. (Not A Separate Pay Item)*

CHARLES ZACHARIAH PANAGIAN
REGISTERED PROFESSIONAL ENGINEER
STATE OF MISSISSIPPI

06/26/2026

CITY OF JACKSON

DESIGNED BY: CZP
DETAILED BY: CZP
CHECKED BY: RCF
DATE: 03/13/2026

FMS CON: 109860/701000
PROJECT NO.: STP-7287-00(001)LPA
COUNTY: HINDS

PRECAST PANEL DETAILS


DIR OF STRUCTURES, STATE BRIDGE ENGINEER - SCOTT WESTERFIELD, P.E.
DEP. DIR OF STRUCTURES, ASST. STATE BRIDGE ENGINEER - MICAH DEW, P.E.

WK. NO. **4 OF 4**


SHEET NO. **8005**

PLAN SHEET


9/15/2026 9:18:46 AM Panels.dgn



ELEVATION – 19' END SPAN & 19' INTERMEDIATE SPAN



ELEVATION – 19' END SPAN & 31' INTERMEDIATE SPAN



ELEVATION – 31' END SPAN & 31' INTERMEDIATE SPAN


GENERAL NOTES

Specifications: Current Mississippi Standard Specifications For State Aid Road And Bridge Construction.


All Units Shall Be Accurately Placed On Preset Caps With All Slab To Cap Dowels Installed And All Bolts, Transverse And Longitudinal, Installed.

Hardware Shall Be Galvanized Or Cadmium Plated.

All Material And Work For Which No Pay Items Are Provided In The Proposal Will Not Be Paid For Directly And Compensation Therefore Will Be Considered Included In The Prices And Payments For Bid Items.



SECTION OF 30'-0" ROADWAY



SECTION OF 28'-0" ROADWAY

PAY ITEMS FOR 30'-0" ROADWAY

End Span Pay Item No.			Quantity	
S-806-A:	19' / 31'	Precast Concrete Slab Unit, 3.5' Interior	4	Each
S-806-A:	19' / 31'	Precast Concrete Slab Unit, 4.5' Interior	2	Each
S-806-C:	19' / 31'	Precast Concrete Slab Unit, 3.5' Exterior	2	Each
S-806-G:		Precast Concrete Barrier Rail	19' 38.0 / 31' 62.0	L.F.
S-806-I:		33.0' Precast Concrete Cap, Steel / Concrete Intermediate Unit, Steel / Concrete Pile	1	Each
S-806-J:		33.0' Precast Concrete Cap, End Unit, Steel / Concrete Pile	1	Each
S-806-M:		10.0' Precast Concrete Wing	2	Each

Intermediate Span Pay Item No.			Quantity	
S-806-A:	19' / 31'	Precast Concrete Slab Unit, 3.5' Interior	4	Each
S-806-A:	19' / 31'	Precast Concrete Slab Unit, 4.5' Interior	2	Each
S-806-C:	19' / 31'	Precast Concrete Slab Unit, 3.5' Exterior	2	Each
S-806-G:		Precast Concrete Barrier Rail	19' 38.0 / 31' 62.0	L.F.
S-806-I:		33.0' Precast Concrete Cap, Steel / Concrete Intermediate Unit, Steel / Concrete Pile	1	Each

PAY ITEMS FOR 28'-0" ROADWAY

End Span Pay Item No.			Quantity	
S-806-A:	19' / 31'	Precast Concrete Slab Unit, 3.5' Interior	6	Each
S-806-C:	19' / 31'	Precast Concrete Slab Unit, 3.5' Exterior	2	Each
S-806-G:		Precast Concrete Barrier Rail	19' 38.0 / 31' 62.0	L.F.
S-806-I:		31.0' Precast Concrete Cap, Steel / Concrete Intermediate Unit, Steel / Concrete Pile	1	Each
S-806-J:		31.0' Precast Concrete Cap, End Unit, Steel / Concrete Pile	1	Each
S-806-M:		10.0' Precast Concrete Wing	2	Each

Intermediate Span Pay Item No.			Quantity	
S-806-A:	19' / 31'	Precast Concrete Slab Unit, 3.5' Interior	6	Each
S-806-C:	19' / 31'	Precast Concrete Slab Unit, 3.5' Exterior	2	Each
S-806-G:		Precast Concrete Barrier Rail	19' 38.0 / 31' 62.0	L.F.
S-806-I:		31.0' Precast Concrete Cap, Steel / Concrete Intermediate Unit, Steel / Concrete Pile	1	Each

DESIGN DATA:

Specifications:.....2007 AASHTO LRFD Bridge Design Specifications, 4th Edition, 2007, Through 2009 Interims

Design Loading:.....HL-93

fy = 60,000 p.s.i.; f'c = 4,500 p.s.i.; n = 7

MBE BY

Rev. AASHTO LRFD 2009 REVISIONS

04-11 DATE

OFFICE OF STATE AID ROAD CONSTRUCTION
MISSISSIPPI DEPARTMENT OF TRANSPORTATION

19' & 31' PRECAST CONCRETE SPANS FOR USE WITH BARRIER RAIL 28'-0" ROADWAY 30'-0" ROADWAY

FHWA APPROVAL 6-10

STATE AID ENGINEER: J. BROOKS MILLER, Sr.


BRIDGE ENGINEER: FRED HOLLIS

DRAWN BY: M.B.E. | ISSUED BY: F.C.H.

DESIGNED BY: M.B.E. | DATE: 06-11


DRAWING NUMBER: PC-02-09

PC02DRWG2830 (N.T.S.) 08/01/2005




PLAN

Bolt All Slabs Transversely At 3 Points. One At Each End And One Near The Center.




PLAN–REINFORCING



ELEVATION INTERIOR UNIT


PAY ITEM S-806-A: 19' Precast Concrete Slab Unit, 3.5' Interior – per each




NOTE: Adjust Bars B2 In Conflict With Holes And Inserts.

ELEVATION EXTERIOR UNIT

PAY ITEM S-806-C: 19' Precast Concrete Slab Unit, 3.5' Exterior – per each




SECTION INTERIOR UNIT




BARS B2 – #3

BARS B1 – #3


BARS B3 – #3



END ELEVATION




KEY DETAIL



SECTION AT DRAIN


BAR BENDING DETAILS

Dimensions Are Out To Out.



SECTION EXTERIOR UNIT

NOTE: Cable Lifting Loops Are Allowed When Located In Keyways, Cut Off Below Deck, And Not Visible After Placing Keyway Grout.



BARRIER RAIL ANCHOR DETAIL

SECTION A–A

GENERAL NOTES:

Specifications: Current Mississippi Standard Specifications For State Aid Road And Bridge Construction.

All Concrete Shall Obtain A Minimum Compressive Strength Of 4,500 p.s.i. At 28 Days, And Shall Obtain A Minimum Compressive Strength Of 2,500 p.s.i. Before Units Are Lifted From Forms.

All Concrete Edges Shall Be Chamfered 3/4" Unless Otherwise Noted.

All Other Concrete Corners Shall Be Rounded To A 1/4" Radius.

All Reinforcing Steel Shall Be A.S.T.M. A615, Grade 60.

Dimensions For Reinforcing Steel Are To The Centerline Of The Bars Unless Otherwise Noted.

All Reinforcing Steel Shall Be Accurately Located In The Forms And Firmly Held In Place By Means Of Steel Wire Supports.

Wire Mesh Shall Conform To "Specification For Welded Deformed Steel Wire Fabric For Concrete Reinforcement" (A.S.T.M. A497) For Deformed Wire And "Specification For Welded Steel Wire Fabric For Concrete Reinforcement" (A.S.T.M. A185) For Smooth Wire.

All Material And Work For Which No Pay Items Are Provided In The Proposal Will Not Be Be Paid For Directly And Compensation Therefore Will Be Considered Included In The Prices And Payments For Bid Items.

DESIGN DATA:

Specifications:.....2007 AASHTO LRFD Bridge Design Specifications, 4th Edition, 2007, Through 2009 Interims

Design Loading:.....HL-93

fy = 60,000 p.s.i.; f'c = 4,500 p.s.i.; n = 7

	BY	MBE
	REVISIONS	Rev. AASHTO LRFD 2007
	DATE	3-09

OFFICE OF STATE AID ROAD CONSTRUCTION
MISSISSIPPI DEPARTMENT OF TRANSPORTATION

19' x 3.5' PRECAST CONCRETE SLAB UNIT FOR USE WITH BARRIER RAIL

FHWA APPROVAL 6-10

STATE AID ENGINEER: J. BROOKS MILLER, Sr.

BRIDGE ENGINEER: FRED HOLLIS

DRAWN BY: M.B.E.


DESIGNED BY: M.B.E.

ISSUED BY: F.C.H.


DATE: 6-11

DRAWING NUMBER: PC-05-09

POSSSPCSL (M.S.) 2-1-2008



PLAN




NOTE: Piles Shall Be In Accordance With Guidelines On Sheet PC-14-09.


ELEVATION
INTERMEDIATE UNIT

Minimum Factored Pile Bearing Capacity
19'-19'~ 52 Tons (STR1)
19'-31'~ 62 Tons (STR1)
31'-31'~ 70 Tons (STR1)

PAY ITEM
S-806-I: 31' Precast Concrete Cap, Steel Intermediate Unit, Concrete Pile - per each.



PLAN




ELEVATION
END UNIT

Minimum Factored Pile Bearing Capacity
19' ~ 33 Tons (STR1)
31' ~ 44 Tons (STR1)


PAY ITEM
S-806-J: 31' Precast Concrete Cap, End Unit, Steel Concrete Pile - per each.

GENERAL NOTES


Specifications: Current Mississippi Standard Specifications For State Aid Road And Bridge Construction.
All Concrete Shall Obtain A Minimum Compressive Strength Of 3000 p.s.i. At 28 Days, And A Minimum Compressive Strength Of 2500 p.s.i. Before Caps Are Lifted From Forms.
The Top Surface Of Caps Shall Have A Rubbed Finish In Accordance With Section S-804.03.19.3.1 Of The Specifications.
All Concrete Edges Shall Be Chamfered 3/4".
Reinforcing Steel Shall Be Deformed Bars Conforming To A.S.T.M. A615 Grade 60. All Reinforcing Steel Shall Be Accurately Located In The Forms And Securely Held In Place By Means Of Steel Wire Supports.
Grout For Cap To Piling Connection Shall Be Non-Shrink Commercial Type Or Epoxy Type In Accordance With Section S-806.03.5 "Handling And Placing Precast Caps, Slabs, Barrier Rail, And Wings" Of The Specifications.
Hardware Shall Be Galvanized Or Cadmium Plated.
All Material And Work For Which No Pay Items Are Provided In The Proposal Will Not Be Paid For Directly And Compensation Therefore Will Be Considered Included In The Prices And Payments For Bid Items.
For Federal Aid Projects This Drawing May Only Be Used In Seismic Zone 1 With Site Classes A, B, C, D & E As Described In The AASHTO LRFD Bridge Design Specifications. The Engineer Must Provide Design Calculations To The Owner Which Confirms The Seismic Zone And Site Class.



TYPICAL END SECTION




TYPICAL INTERIOR SECTION




BARS B - #5 BARS C - #5

BAR BENDING DETAILS
Dimensions Are Out To Out



NEOPRENE BEARING PADS
See Plan No. PC-15-09 For Details



DETAIL "A"

DESIGN DATA:

Specifications:.....A.A.S.H.T.O. LRFD BRIDGE DESIGN SPECIFICATIONS, 4th EDITION, 2007, THROUGH 2009 INTERIMS
Design Loading:.....HL-93
fy = 60,000 p.s.i. fc = 3,000 p.s.i. n = 9

FHWA APPROVAL: 6-10			
STATE AID ENGINEER: J. BROOKS MILLER, Sr.			
BRIDGE ENGINEER: FRED HOLLIS			


DATE	REVISIONS	BY
09-11	Revised Exp. Joint Filler Spec.	JDW
04-11	REVISED AASHTO LRFD 2009	MBE

OFFICE OF STATE AID ROAD CONSTRUCTION
MISSISSIPPI DEPARTMENT OF TRANSPORTATION


PRECAST CONCRETE CAPS FOR USE WITH 19 FT. & 31 FT. PRECAST CONCRETE SPANS & BARRIER RAIL 28'-0" ROADWAY

DRAWN	ISSUED BY:	DRAWING NUMBER:
M.B.E	F.C.H.	PC-12-09
DESIGNED: M.B.E	DATE: 6-11	


PC12CAP28 (N.T.S.) 09/11/2009




TYPE AS TYPE BS




TYPE CS TYPE DS




TYPE ES TYPE FS




TYPE GS




TYPE HS



PLAN – INTERMEDIATE CAP UNIT




PLAN – INTERMEDIATE CAP UNIT



PLAN – END CAP UNIT


NEOPRENE PAD PLACEMENT – 23' & 24' CLEAR ROADWAYS




NOTE: For 26.5' Caps Use Type AS Pads At Ends Instead Of Type ES Pads.

PLAN – END CAP UNIT


NEOPRENE PAD PLACEMENT – 26.5',28',& 30' CLEAR ROADWAYS




TYPE A TYPE B TYPE C TYPE D TYPE E



PLAN – INTERMEDIATE CAP UNIT




PLAN – INTERMEDIATE UNIT



PLAN – END CAP UNIT

NEOPRENE PAD PLACEMENT – 23' & 24' CLEAR ROADWAYS



NOTE: For 26.5' Caps Use Type A Pads At Ends Instead Of Type E Pads.

PLAN – END CAP UNIT

NEOPRENE PAD PLACEMENT – 26.5',28',& 30' CLEAR ROADWAYS

GENERAL NOTES:

Specifications:
- Hardness A.S.T.M. D2240 70 Durometer ±5
- Tensile Strength A.S.T.M. D412 2500
- Ultimate Elongation Minimum % 300

All Holes Are 2 Inches In Diameter
Thickness Of The Pads Shall Be 1/4" Unless Otherwise Designated On The Plans. Pads May Be Cut From Stock Using Appropriate Saw Or Shear, And Holes May Be Drilled. Pads Will Not Be Paid For Separately And Compensation Therefore Shall Be Considered Included In The Prices And Payment For Bid Items.

DESIGN DATA:

Specifications:.....A.A.S.H.T.O. LRFD BRIDGE DESIGN SPECIFICATIONS, 4th EDITION, 2007, THROUGH 2009 INTERIMS

FHWA APPROVAL	6-10		
STATE AID ENGINEER:	J. BROOKS MILLER, Sr.		
BRIDGE ENGINEER:	FRED HOLLIS		


REVISIONS	DATE	BY
Rev AASHTO LRFD 2009	4-11	MBE

OFFICE OF STATE AID ROAD CONSTRUCTION
MISSISSIPPI DEPARTMENT OF TRANSPORTATION


BEARING PAD & PLACEMENT DETAILS FOR USE WITH 23',24',26.5',28',&30' CLEAR ROADWAYS NORMAL AND 30° SKEW SPANS

DRAWN BY:	ISSUED BY:	DRAWING NUMBER:
M.B.E.	F.C.H.	PC-15-09
DESIGNED BY: M.B.E.	DATE: 6-11	


PC-15 PADS (N.T.S.) 06/01/2005




PART PLAN




PART ELEVATION



SECTION A–A



SLOT DETAIL



BARS A – #5

BAR BENDING DETAILS

Dimensions Are Out To Out

GENERAL NOTES

Specifications: Current Mississippi Standard Specifications For State Aid Road And Bridge Construction.

All Concrete Shall Obtain A Minimum Compressive Strength Of 3000 p.s.i At 28 Days, And Shall Obtain A Minimum Compressive Strength Of 2500 p.s.i. Before Units Are Lifted From Forms.

All Concrete Edges Shall Be Chamfered 3/4" Unless Otherwise Noted.

All Concrete Corners Shall Be Rounded To A 1/4" Radius.

All Reinforcing Steel Shall Be A.S.T.M. A615, Grade 60.

Dimensions For Reinforcing Steel Are To The Centerline Of The Bars, Unless Otherwise Noted.

All Reinforcing Steel Shall Be Accurately Located In The Forms And Firmly Held In Place By Means Of Steel Wire Supports.


All Hardware Shall Be Galvanized Or Cadmium Plated.

All Material And Work For Which No Pay Items Are Provided In The Proposal Will Not Be Paid For Directly And Compensation Therefore Will Be Considered Included In The Prices And Payments For Bid Items.

DESIGN DATA:


Specifications:.....A.A.S.H.T.O. LRFD BRIDGE DESIGN SPECIFICATIONS, 4th EDITION, 2007, THROUGH 2009 INTERIMS

PAY ITEM
S-806-M: 9.25' Precast Concrete Wing – per each.




ELEVATION

LEFT WING
Showing Concrete Dimensions



RIGHT END ELEVATION

SECTION B–B



RIGHT WING
Showing Reinforcing

ELEVATION

OFFICE OF STATE AID ROAD CONSTRUCTION
MISSISSIPPI DEPARTMENT OF TRANSPORTATION

PRECAST ABUTMENT WINGWALL
FOR USE WITH 19 FT. & 31 FT. PRECAST
CONCRETE SPANS & BARRIER RAIL
28 FT. & 30 FT. ROADWAYS


REVISIONS	DATE	BY
Rev. Exp. Joint Filler Note	09-11	JDM
Rev. AASHTO LRFD 2009	4-11	MBE

FHWA APPROVAL 6-10
STATE AID ENGINEER: J. BROOKS MILLER, Sr.
BRIDGE ENGINEER: FRED HOLLIS


DRAWN BY: M.B.E | ISSUED BY: F.C.H.
DESIGNED BY: M.B.E | DATE: 6-11

DRAWING NUMBER: PC-17-09

PC017PAW (N.T.S.) 06/01/2005




END SPAN **PLAN** **INTERMEDIATE SPAN**




END SPAN **ELEVATION** **INTERMEDIATE SPAN**


NOTE: Block Out Bottom Corners Of Right Rail For Right Forward Skew, And Left Rail For Left Forward Skew To Clear Precast Wings.



BARS E – #5




BARS DB – #5



KEYWAY DETAIL


PAY ITEM
S-806-C: Precast Concrete Barrier Rail – per linear foot



L1 Bars – #4
L2 Bars – #6
LT Bars – #6 x 7'-0" @ Transition
LB Bars – #4 x 3'-2" @ End Block

Note: L1 & L2 Bars Not Shown For Clarity.

TYPICAL SECTION



END ELEVATION

GENERAL NOTES

Specifications: Current Mississippi Standard Specifications For State Aid Road And Bridge Construction.

All Concrete Shall Obtain A Minimum Compressive Strength Of 3,000 p.s.i. At 28 Days. And Obtain A Minimum Compressive Strength Of 2,500 p.s.i. Before Units Are Lifted From Forms.

Reinforcing Steel Shall Be Deformed Bars Conforming To A.S.T.M. A615, Grade 60. All Reinforcing Steel Shall Be Accurately Located In The Forms And Securely Held In Place By The Means Of Steel Wire Supports.


Screw Anchor And Bolt Assembly Shall Be 2" ø x 2'-11" As Manufactured By Richmond Screw And Anchor Co., Inc. Or Equal. Assembly Shall Be Galvanized In Accordance With A.S.T.M. A153. Minimum Ultimate Strength In Tension Shall Be 112,000 Lbs. Anchor Plate Washers For Screw Anchor Bolts Shall Be 7 1/2" x 7 1/2" x 7/8" Steel Plate, A.S.T.M. A123.

All Material For Which No Pay Items Are Provided In The Proposal Will Not Be Paid For Directly And Compensation Therefore Will Be Considered Included In The Prices And Payments For Bid Items.


DESIGN DATA:

Specifications:.....A.A.S.H.T.O. LRFD BRIDGE DESIGN SPECIFICATIONS, 4th EDITION, 2007, Through 2009 Interims


BARS S1 – #4




BARS RB – #4



BARS R1 – #4



BARS D3 & D4 – #4



BARS D1 & D2 – #4

BAR BENDING DETAILS
Dimensions Are Out To Out.

			MBE	BY
			4-11	Rev. AASHTO LRFD 2009
				REVISIONS

OFFICE OF STATE AID ROAD CONSTRUCTION
MISSISSIPPI DEPARTMENT OF TRANSPORTATION


19'–0" SOLID TYPE BARRIER RAIL


FHWA APPROVAL 6-10
STATE AID ENGINEER: J. BROOKS MILLER, Sr.
BRIDGE ENGINEER: FRED HOLLIS


DRAWN BY: M.B.E
DESIGNED BY: M.B.E
ISSUED BY: F.C.H.
DATE: 6-11
DRAWING NUMBER: PC–18–09


PC018Rail19 (SF-12) 2-15-2006

CROSS SECTION SHEET









KOHL BOOLER
LICENSED PROFESSIONAL ENGINEER
35697
STATE OF MISSISSIPPI
06/26/2026

CITY OF JACKSON


DESIGNED BY: RKB
DETAILED BY: RKB
CHECKED BY: FMT
DATE: 6/26/2026


FMS CON: 109860/701000
PROJECT NO.: STP-7287-00(001)LPA
COUNTY: HINDS

ML_MCCLUER
STA. 9+40.00 - STA. 10+50.00

SHEET NO.
9001

6/26/2026 2:08:12 PM XS-McCluer.dgn





CROSS SECTION SHEET

6/26/2026 2:08:12 PM XS-McCluer.dgn

KOHL BOOZER
LICENSED PROFESSIONAL ENGINEER
35697
STATE OF MISSISSIPPI
06/26/2026

CITY OF JACKSON

DESIGNED BY: RKB
DETAILED BY: RKB
CHECKED BY: FMT
DATE: 6/26/2026

FMS CON: 109860/701000
PROJECT NO.: STP-7287-00(001)LPA
COUNTY: HINDS

ML_MCCLUER
STA. 11+00.00 - STA. 11+40.00

SHEET NO.
9002